

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in

<u>Oakland</u> <small>(County)</small>	Located in: <u>Oxford</u> Twp.	Corner Code <u>#</u> <u>K-4</u>
1. Public Land Survey	T <u>5N</u> R <u>10E</u>	<u>K-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

\$ 7.00 MISCELLANEOUS RECORDING
 \$ 2.00 REMONUMENTATION
 24 OCT 94 8:51 A.M. RECEIPT# 33B
 PAID RECORDED - OAKLAND COUNTY
 LYNN D. ALLEN, CLERK REGISTER OF DEEDS
 ACT 345, P.A. 1990

APPROVED ON: 9-7-94
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

I, Huston K. Kennedy, in a field survey on July 25, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 1818-GLO Wampler, D.S.; Set Post; 18" Black Oak S89°W 2.91 Links
 1.) 1982-Kennedy, P.S. #17623; LCRC L.8273, Pg.791 - Fnd 1" Iron Pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1" Iron Pipe that is located 4" under the road surface and in the centerline of North Oxford Road, which is gravel surface with a tree row extending East and West, also the North line of the "North Oxford Cemetery".

Witnesses from LCRC #1 were used to recover and verify the location of found 1" Iron Pipe.
 I accepted the found 1" Iron Pipe as the best evidence of the original corner position.

*7.00
2.00
file*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-4 I replaced the found 1" Iron Pipe with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623.
 N31°W 67.49' Set PK & Remon. Washer NE face 34" Oak
 S37°W 54.90' Set PK & Remon. Washer SE face 10" Elm
 S40°E 59.54' Set PK & Remon. Washer SW face 21" Maple
 S72°E 35.32' Set PK & Remon. Washer SW face 24" Maple

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by [Signature] Date September 8, 1994
 Surveyor's Michigan License No. 17623