

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in

Form with fields for County (Oakland), Located In (Oxford Twp.), Corner Code (# K-5), and numbered sections 1-5 for Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

Stamp area containing recording fees (\$7.00 MISCELLANEOUS RECORDING, \$2.00 REMONUMENTATION), date (25 OCT 94 8:33 A.M.), receipt number (44B), and signatures of Lynn D. Allen and approval of Oakland County Remonumentation Peer Group Committee.

Register of Deeds Stamp & File Number

Grid table with columns A-K and rows 1-13, used for recording corner locations. A dot is marked at row 5, column J.

I, Huston K. Kennedy, in a field survey on August 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post; 18" White Oak N50°E 3.60 Chains; 24" White Oak S86°W 4.27 Chains
1.) 1975-Heil, P.S. #18993; LCRC L.6587, Pg.375 - Fnd 1/2" Iron Rod
2.) 1982-Kennedy, P.S. #17623; LCRC L.8273, Pg.791 - Fnd 1/2" Iron Rod
3.) 1975-Heil, P.S. #18933; Survey L.6509, Pg.783 - Fnd 1/2" Iron Rod, used same wit as 1975 LCRC
4.) 1986-Heil, P.S. #18933; Unrecorded Survey - Fnd 1/2" Iron Rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod that is located 7" under the road surface and 2' South of the center of Noble Road to the East and 2' East of the center of Oxford Road to the North, and 1' South of the center of Oxford Road to the West. Both are gravel surface roads.

Witnesses from LCRC #1 were used to recover and verify the location of the 1/2" Iron Rod.

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-5 I replaced the found 1/2" Iron Rod with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, P.S. #17623.
Due South 60.70' Set PK & Remon. Washer East face Power Pole
S16°W 46.15' Set PK & Remon. Washer East face 9" Elm
S24°W 48.84' Set PK & Remon. Washer East face 10" Elm
N63°E 70.82' Set PK & Remon. Washer SE face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by [Signature] Date September 1, 1994
Surveyor's Michigan License No. 17623