

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in Oakland

Table with columns: (County), Located In: Oxford Twp., Corner Code #. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec.

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
25 OCT 94 8:34 A.M. RECEIPT# 448
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
ACT 345, P.A. 1990

APPROVED ON: 9-14-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, Huston K. Kennedy in a field survey on August 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-K and rows 2-13. A dot is marked at row 6, column J.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1818-GLO Wampler, D.S.; Set Post; 8" White Oak N20°E 24 Links; White Oak S26°W 24 Links
1.) 1984-Kennedy, P.S. #17623; LCRC L.8789, Pg.452 - Fnd 1/2" Iron Rod
2.) 1982-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 1/2" Iron Rod
3.) 1985-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 1/2" Iron Rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod 3" above ground at a four way fence corner and tree row extending to the East, West, North & South.

Witnesses from LCRC #1 were used to recover and verify the location of the found 1/2" Iron Rod.

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-6 I replaced the found 1/2" Iron Rod with 1/2" Iron Rod encased in a 4" diameter concrete cylinder 36" long w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623.
Due North 24.42' Set PK & Remon. Washer West face 27" Oak
N83°E 8.87' Set PK & Remon. Washer North face 9" Cherry
Due South 2.77' Set PK & Remon. Washer East face 22" Oak
S46°E 18.43' Set PK & Remon. Washer NE face 11" Cherry

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by [Signature]
Surveyor's Michigan License No. 17623

Date September 8, 1994