

COPY

JUL 14 95 125248

LIBR 15517c416

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Oakland (County)

Located In: Oxford Twp. Corner Code #

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
14 JUL 95 8:39 A.M. RECEIPT# 98
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

- 1. Public Land Survey T 5N R 10E K-8
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R

Compliance with ACT 345, P.A. 1990

APPROVED ON: 6-21-95
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 1-13. A dot is marked at the intersection of column K and row 8.

Huston K. Kennedy, in a field survey on April 26, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1818-GLO Wampler, D.S.; Set Post 10" Black Oak N63°W 94 Links; 36" White Oak S55°E 223 Links
No Land Corner Recordation Certificates (LCRC) or Certificates of Survey were found for this corner

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Due to the gravel mining operation, there are no line or occupation to the North, South, East or West.

To recover this corner, I used single GLO proration between K-7 and K-9. Due to the very deep excavation, which was in the process of being filled. I set a reference corner on the line between K-7 and K-9, 60.00 feet North of the corner.

FIELD MEASUREMENTS BETWEEN

- K-7 to K-9 5675.75 Ft., GLO = 80 chains or 5280.00 Ft.
K-7 to K-8 3128.47 Ft., GLO = 40 chains or 2640.00 Ft.
K-8 to K-9 3128.48 Ft., GLO = 40 chains or 2640.00 Ft.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8 I set a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623, 60.00 feet North of K-8 as a reference corner
N15°W 15.65' Set PK & Remon. Washer West face 8" Poplar
S87°W 47.93' Set PK & Remon. Washer North face 13" Poplar
N71°E 22.40' Set PK & Remon. Washer SE face 9" Cherry
N82°E 18.32' Set PK & Remon. Washer SE face 6" Oak

The selected location for this reference corner is accepted as a careful and faithful determination of the position as indicated.

Signed by [Signature]
Surveyor's Michigan License No. 17623

Date June 15, 1995



7.00
2.00