

**SURVEY & REMONUMENTATION**

MAY 16 1996

LIBER 15796pc533

05218287

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Oakland Located In: Oxford Twp. Corner Code #  
(County)

- |                                      |             |              |             |
|--------------------------------------|-------------|--------------|-------------|
| 1. Public Land Survey                | T <u>5N</u> | R <u>10E</u> | <u>K-11</u> |
|                                      | T           | R            |             |
|                                      | T           | R            |             |
|                                      | T           | R            |             |
| 2. Property Controlling in Section   | S           | T            | R           |
|                                      | S           | T            | R           |
| 3. Miscellaneous Property in Section | S           | T            | R           |
|                                      | S           | T            | R           |

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
6 NOV 95 9:01 A.M. RECEIPT# 8A  
PAID COMPLIANCE WITH ACT 74 OF 1970 OAKLAND COUNTY  
LYNN D. ALLEN, CLERK REGISTER OF DEEDS  
APPROVED ON: 10/10/95  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Huston K. Kennedy in a field survey on August 10, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1818-GLO Wampler, D.S.; Post not set, falls in a lake  
1.) 1973-Buckerfield, PS #10868; LCRC L.6260, Pg.658 - Set 1/2" Iron Bar in Mud Lake  
2.) 1995-Orchard, Hiltz & McCliment, Inc., - Unrecorded witnesses

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1/2" Iron Pipe 5" above the water surface in a swamp. A fence-tree row extending to the South. The corner is located 30 feet ± South of the water's edge of Mud Lake.

The unrecorded witnesses from Orchard, Hiltz & McCliment, Inc. were used to recover and verify the location of the found 1/2" Iron Pipe.

I accepted the found 1/2" Iron Pipe as the best evidence of the original corner position.

**FIELD MEASUREMENTS BETWEEN**

K-11 to J-11 2769.19 Ft., GLO = 40 chains or 2640.00 Ft.  
K-11 to K-12 3059.50 Ft., GLO = 40 chains or 2640.00 Ft.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- K-11 I replaced the found 1/2" Iron Rod Pipe with a 5/8" x 60" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623  
N82°W 48.29' Set PK & Remon. Washer South face 14" Willow  
S53°W 62.00' Set PK & Remon. Washer SE face 10" Poplar  
S81°W 59.65' Set PK & Remon. Washer South face 12" Elm  
N33°E 47.52' Set PK & Remon. Washer SE face 9" Elm

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]  
Surveyor's Michigan License No. 17623

Date October 10, 1995

7.00  
2.00  
amt  
file

