

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

OK - T. SMITH

For corners in

Oakland  
(County)

Located In: Oxford Corner Code ##  
Township

- |                                    |   |          |   |   |           |   |            |
|------------------------------------|---|----------|---|---|-----------|---|------------|
| 1. Public Land Survey              | T | <u>5</u> | N | R | <u>10</u> | E | <u>L-3</u> |
|                                    | T |          | R |   |           |   |            |
|                                    | T |          | R |   |           |   |            |
|                                    | T |          | R |   |           |   |            |
| 2. Property Controlling in Section | S |          | T |   | R         |   |            |
|                                    | S |          | T |   | R         |   |            |
| 3. Miscellaneous Property in Sec.  | S |          | T |   | R         |   |            |
|                                    | S |          | T |   | R         |   |            |

\$ 7.00 MISCELLANEOUS RECORDING  
 \$ 2.00 REMONUMENTATION  
 8 SEP 94 3:20 P.M. RECEIPT# 1348  
 PAID RECORDED - OAKLAND COUNTY  
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS  
 Compliance with  
 ACT 345, P.A. 1990

APPROVED ON: 1-5-94  
 OAKLAND COUNTY REMONUMENTATION  
 PEER GROUP COMMITTEE  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Huston Kennedy, in a field survey on November 4, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1817 GLO - Wampler, D.S.; Set post; 10" ? S18 1/2°E 0.81 lks., 12" ? N06 1/2°E 2.17 lks.
- 1977 Henderson, P.S. #16043; Survey L.7041, Pg.339 - Fnd 1" iron pipe
- 1982 Kennedy, P.S. #17623; LCRC L.8256, Pg.502 - Fnd 1 1/2" iron pipe

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1993 Kennedy Surveying, Inc. - Huston Kennedy, P.S. #17623 - Found 1" iron pipe in the intersection of the center of Oakwood Road and Delano Road. Both are gravel roads. The witness trees still exist, but the witness points are grown over. The witness trees were used to recover and verify the found iron pipe.

I accepted the found iron pipe as the best evidence of the original corner position.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

L-3 I replaced the found 1" iron pipe with a 5/8" x 24" iron rod with a 2" diameter cap stamped Oakland County Remonumentation P.S. #17623.

- N30°E-54.39 ft-Set PK/Remon. Tag above existing witness SE face 22" Cherry
- N53°W-71.15 ft-Set PK/Remon. Tag below existing witness SW face Power pole
- S20°E-73.04 ft-Set PK/Remon. Tag above existing witness West face 27" Oak
- S59°W-82.69 ft-Set PK/Remon. Tag NW face 21" Oak

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original position.

Signed by [Signature]  
 Surveyor's Michigan License No. 17623

Date March 23, 1994

