

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in

Oakland
(County)

Oxford

Located In: Twp.

Corner Code #

- 1. Public Land Survey T 5N R 10E L-5
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
24 OCT 94 8:51 A.M. RECEIPT# 33B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
ACT 345, P.A. 1990

APPROVED ON: 9-14-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, Huston K. Kennedy, in a field survey on August 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 1-13. A dot is marked at row 5, column K.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1818-GLO Wampler, D.S.; Set Post; 12" White Oak N61\*W 2 Links; 12" White Oak S21\*E 50 Links
1.) 1978-Henderson, P.S. #16043; LCRC L.7300, Pg.666 - Fnd 1/2" Iron Rod
2.) 1978-Henderson, P.S. #16043; Survey L.7300, Pg.655 - Fnd 1/2" Iron Rod, same wit as 1978 LCRC
3.) 1987-Scharl, P.S. #19843; Survey L.10108, Pg.774 - Fnd 3/8" Iron rod
4.) 1987-Scharl, P.S. #19843; Survey L.10108, Pg.780 - Fnd 3/8" Iron Rod
5.) 1987-Scharl, P.S. #19843; Survey L.10108, Pg.786 - Fnd 3/8" Iron Rod
6.) Oakland County Road Commission; Unrecorded Witnesses - Fnd Iron Pipe
7.) 1977-Jones, P.S. #16045; Unrecorded Survey - Fnd 3/8" Iron Rod
8.) 1980-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 1/2" Iron Rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod located 8" under the road surface and in the center of Noble Road and 3' West of the center of Delanno Road. Both are gravel roads.

Witnesses from LCRC #1, Survey #2 were used to recover and verify the location of the found 1/2" Iron Rod.

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

Handwritten note: 7.00 Paid, 2.00 file

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-5 I replaced the found 1/2" Iron Rod with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, P.S. #17623.

- N63°W 86.10' Set PK & Remon. Washer South face 10" Cherry
S46°W 49.23' Set PK & Remon. NW face 13" Elm
S48°E 73.02' Set PK & Remon. SW face 17" Twin Cherry
N52°E 59.91' Set PK & Remon. SE face 9" Cherry

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by [Signature]
Surveyor's Michigan License No. 17623

Date September 15, 1994