

Oct 24 94 278822

LIBER 15053 PG 079

OK - T. SMITH

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oakland

(County)

Located In: Oxford Twp.

Corner Code #

- 1. Public Land Survey T 5N R 10E L-7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
24 OCT 94 8:51 A.M. RECEIPT# 33B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990

APPROVED ON: 9-14-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Huston K. Kennedy in a field survey on July 25, 1994 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1818-GLO Wampler, D.S.; Set Post; 12" White Oak N81°E 79 Links; 12" White Oak S82°W 88 Links
1.) 1978-Jones, P.S. #16045; LCRC L.7177, Pg.598 - Fnd 1/2" Iron Rod
2.) 1975-Jones, P.S. #16045; Unrecorded Survey - Fnd 1/2" Iron Rod
3.) 1980-Scharl, P.S. #19843; Unrecorded Survey - Fnd 1/2" Iron Rod
4.) 1983-Buckerfield, P.S. #10868; Unrecorded Survey - Fnd 1/2" Iron Rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod located 5" under the road surface and 5' East of the center of Delano Road to the North and 4' North of the center of Ray Road to the East & West. Both are gravel surface roads. Tree and rock row extending to the South.

Witnesses from LCRC #1 & 4 were used to recover and verify the location of the found 1/2" Iron Rod.

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7 I replaced the found 1/2" Iron Rod with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623.

- N43°W 80.44' Set PK & Remon. Washer SW face Power Pole
N57°E 53.34' Set PK & Remon. Washer NW face 27" Walnut
S32°W 33.58' Set PK & Remon. Washer SE face 26" Oak
S72°E 48.12' Set PK & Remon. Washer NE face 27" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]
Surveyor's Michigan License No. 17623

Date September 15, 1994



7.00 file
2.00 file