

LIBER 15212 PG 866

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in
Oakland
(County)

Located In: Oxford Twp. Corner Code #

7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
20 JAN 95 7:29 A.M. RECEIPT# 68
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Table with 3 columns: Description (Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec.), Direction (S, T, R), and Corner Code (L-9).

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-14-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 2-12. A dot is marked in the cell corresponding to column K and row 9.

I, Huston K. Kennedy, in a field survey on December 2, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post 12" White Oak N40°E 32 Links; 15" Black Oak S56°W 22 Links
1.) 1986-Kennedy, P.S. #17623; L.9248, Pg.637 - Fnd 1/2" Iron Rod in the center of Lakeville Road. Fnd P.K. Nail 2.11' to the South
2.) 1993-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 1/2" Iron Rod in a Monument Box
3.) 1993-Kennedy, P.S. #17623; Unrecorded Survey - Fnd 1/2" Iron Rod in a Monument Box, used same wit as 1993 Unrecorded Survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod in a Monument Box located in the center of Lakeville Road which has a bituminous surface. No lines of occupation extending to the North or South.

Witnesses from Recorded Survey #1 and Unrecorded Survey #2 were used to recover and verify the location of the 1/2" Iron Rod in a Monument Box.

I accept the 1/2" Iron Rod in a Monument Box as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

- L-9 to H-9 2465.61 Ft. (H. Kennedy 1977)
L-9 to K-9 2737.14 Ft. (H. Kennedy 1993)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9 I replaced the found 1/2" Iron Rod with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS, #17623 in a existing Monument Box.
N71°W 164.93' Set PK & Remon. Washer SW face Power Pole
N04°W 54.05' Set PK & Remon. Washer West face Power Pole
N71°E 174.82' Set PK & Remon. Washer NW face Power Pole
S80°E 143.70' Set PK & Remon. Washer NW face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by [Signature]
Surveyor's Michigan License No. 17623

Date December 16, 1994