

JAN 20 95 011181

LIBER 15212 PG 867

OK - T. SMITH

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
20 JAN 95 7:29 A.M. RECEIPT# 68  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in  
Oakland  
(County)

Located In: Oxford Corner Code #    
Twp.

1. Public Land Survey	T <u>5N</u>	R <u>10E</u>	<u>M-5</u>
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 12-14-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Huston K. Kennedy, in a field survey on August 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1818-GLO Wampler, D.S.; Set Post; 24" White Oak N12\*W 1.95 Links; 12" White Oak S47\*E 2.20 Links
- 1.) 1978-Henderson, P.S. #16043; LCRC L.7300, Pg.666 - Fnd 1/2" Iron Rod
- 2.) 1994-Antcliff, P.S. #25826; Remonumentation LCRC L.14833, Pg.153 - Fnd 1/2" Iron Bar
- 3.) 1987-Scharl, P.S. #19843; Survey L.10108, Pg.795 - Fnd 1/2" Iron Rod
- 4.) 1989-Bates, P.S. #16699; Survey L.10855, Pg.96 - Fnd 1/2" Iron Rod
- 5.) 1977-Oakland County Road Commission - Unrecorded Witnesses - Fnd 1/2" Iron Rod
- 6.) 1977-Jones, P.S. #16045; Unrecorded Survey - Fnd 1/2" Iron Rod, used same wit as 1987 Survey
- 7.) 1983-Elrich, P.S. #18986; Unrecorded Survey - Fnd 1/2" Iron Rod
- 8.) 1987-Elrich, P.S. #18986; Unrecorded Survey - Fnd 1/2" Iron Rod
- 9.) 1987-Elrich, P.S. #18986; Unrecorded Survey - Fnd 1/2" Iron Rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 5/8" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation PS, #25826 that is located 3" under the road surface and 3' South of the center of Noble Road, which is gravel surface. There is a tree-fence line extending to the South. Also a tree-fence line extending to the North 15.4' West of corner.

Witnesses from LCRC #1, Survey #2 & 3 were used to recover and verify the location of the 5/8" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation PS, #25826.

I accepted the found 5/8" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation PS, #25826 as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-5 I found a 5/8" x 24" Iron Rod w/2" diameter cap stamped Oakland County Remonumentation, PS #25826.
- N07°W 85.58' Fnd PK & Remon. Washer West face 19" Cherry
- N51°E 94.67' Fnd PK & Remon. Washer NW face Power Pole
- S68°E 57.88' Fnd PK & Remon. Washer North face 39" Oak
- S08°E 27.50' Fnd PK & Remon. Washer East face 26" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best evidence of the position of the original corner.



Signed by Huston Kennedy  
Surveyor's Michigan License No. 17623

Date December 16, 1994