

LAND CORNER RECORDATION CERTIFICATE 7.00 MISCELLANEOUS RECORDING
Filing Requirement of Act 74, Mich. P.A. 1970 2.00 REMONUMENTATION

For corners in

Oakland
(County)

Located In: Oxford
Twp.

Corner Code ##

1 FEB 95 8:53 A.M. RECEIPT# 98
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

OK - T. SMITH

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 09-14-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

| | | | | | |
|------------------------------------|---|----|---|-----|-----|
| 1. Public Land Survey | T | 5N | R | 10E | M-6 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

- 4. Lot No. _____ Recorded Plat _____
- 5. Private Claims _____

I, Huston K. Kennedy, in a field survey on October 20, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| A | B | C | D | E | F | G | H | I | J | K | L | N |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1818-GLO Wampler, D.S.; Set Post; 6" Tamarac N05*W 6 Links; 6" Tamarac S20*E 8 Links
- 1.) 1987-Kennedy, P.S. #17623; LCRC L.10013, Pg.218 - End 1/2" Iron Rod
- 2.) 1977-Oakland County Road Commission; Unrecorded Witnesses - End 3/8" Iron Rod
- 3.) 1977-Jones, P.S. #16045; Unrecorded Survey - End 3/8" Iron Rod
- 4.) 1983-Buckerfield, P.S. #10868; Unrecorded Survey - End 1/2" Iron Rod
- 5.) 1988-Kennedy, P.S. #17623; Unrecorded Survey - End 1/2" Iron Rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - End 1/2" Iron Rod in a swamp at a fence corner.
Witnesses from LCRC #1 were used to recover and verify the location of the found 1/2" Iron Rod.
I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6 January 11, 1995, I found a 4" diameter Concrete Monument w/2" diameter brass cap stamped Oakland County Remonumentation, PS #25854
N87°W 18.98' Set PK & Remon. Washer North face 9" Maple
N04°E 16.68' Set PK & Remon. Washer West face clump Maple
Due East 7.81' Set PK & Remon. Washer South face triple Ash
Due South 18.74' Set PK & Remon. Washer East face 13" Elm

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available position of the original corner.



Signed by Huston K. Kennedy
Surveyor's Michigan License No. 17623

Date January 12, 1995