

**SURVEY & REMONUMENTATION**

LIBER 15053 P. 081

OCT 24 94 278824

JUL 29 1996

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in  
Oakland  
(County)

Located In: Oxford  
Twp. Corner Code #/

1. Public Land Survey	T	<u>5N</u>	R	<u>10E</u>	<u>M-7</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	<u>Seg. # 1</u>
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
24 OCT 94 8:52 A.M. RECEIPT# 338  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS  
Compliance with ACT 345, P.A. 1990  
APPROVED ON: 9-14-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6											
3												
4	7	8	9	10	11							
5												
6	18	17	16	15	14							
7												
8	19	20	21	22	23							
9												
10	30	29	28	27	26							
11												
12	31	32	33	34	35							
13												

I, Huston K. Kennedy, in a field survey on July 25, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:  
1818-GLO Wampler, D.S.; Set Post; 12" White Oak N62°E 28 Links; 10" White Oak S67°W 1.35 Chains  
1.) 1987-Kennedy, P.S. #17623; LCRC L.10013, Pg.218 - Fnd 1/2" Iron Rod  
2.) 1983-Buckerfield, P.S. #10868; Unrecorded Survey - Fnd 1/2" Iron Rod

**\*SUPERSEDED BY LIBER 15232 PAGE 613\***

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod with a tree row extending to the East. The corner is 252' South of the centerline of Ray Road which is gravel, and in the centerline of Ballantyne Road, which is a private road with gravel surface.

Witnesses from LCRC #1 were used to recover and verify the location of the found 1/2" Iron Rod.

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

*700 B  
200 B  
file*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
M-7 I replaced the found 1/2" Iron Rod with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, P.S. #17623.

- N12°E 41.32' Set PK & Remon. Washer West face 16" Oak
- N84°E 30.60' Set PK & Remon. Washer South face 9" Maple
- S78°W 38.81' Set PK & Remon. Washer South face 18" Oak
- N43°W 59.50' Set PK & Remon. Washer SW face 12" Maple



The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Huston K. Kennedy  
Surveyor's Michigan License No. 17623

Date September 15, 1994