

JUL 14 95 125253

LIBER 15517 PG 421

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 \$ 7.00 MISCELLANEOUS RECORDING

For corners in Oakland (County)

Located In: Oxford Twp. Corner Code #

\$ 2.00 REMONUMENTATION  
14 JUL 95 8:39 A.M. RECEIPT# 98  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

1. Public Land Survey	T <u>5</u> N	R <u>10</u> E	<u>M-8</u>
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Section	S	T	R
	S	T	R

Compliance with ACT 345, P.A. 1990

APPROVED ON: 6-21-95 Tom S  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
6											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Huston K. Kennedy, in a field survey on April 26, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1818-GLO Wampler, D.S.; Set Post 36" Pine S25°W 54 Links
- 1.) 1977-Kennedy, PS #17623; Unrecorded Survey - Fnd 3/8" Iron Rod
- 2.) 1990-Kennedy, PS #17623; Unrecorded Survey - Fnd 3/8" Iron Rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 3/8" Iron Rod at the surface in the woods with an old fence row extending 1/4 the North, South & West. This corner is also being used and accepted as a common corner with the West 1/4 corner of Section 14 T5N, R11E, Addison Twp. (A-8)

Witnesses from Unrecorded Survey #1 & 2 were used to recover and verify the location of the found 3/8" Iron Rod.

I accepted the found 3/8" Iron Rod as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

- M-8 to M-7 2605.22 Ft., GLO = 40 chains or 2640.00 Ft.
- M-8 to M-9 2851.48 Ft., GLO = 40 chains or 2640.00 Ft.

7.00  
2.00

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-8 I replaced the found 3/8" Iron Rod with a 1/2" Iron Rod encased in a 4" diameter concrete cylinder 36" long w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623
- N03°W 9.17' Set PK & Remon. Washer West face 24" Oak
- N83°W 21.70' Set PK & Remon. Washer NE face 10" Oak
- S39°W 29.17' Set PK & Remon. Washer SE face 10" Oak
- S65°E 41.10' Set PK & Remon. Washer SW face 23" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence position of the original corner.

Signed by: [Signature]  
Surveyor's Michigan License No. 17623

Date June 15, 1995

