

LAND CORNER RECORDATION CERTIFICATE

OK - T. SMITH

Filing Requirement of Act 74, Mich. P.A. 1976

7.00 MISCELLANEOUS RECORDING

\$ 2.00 REMONUMENTATION

20 JAN 95 7:35 A.M. RECEIPT# 88
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in

Oakland
(County)

Located In: Oxford Corner Code #
Twp.

- 1. Public Land Survey T 5N R 10E M-9
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 12-27-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

- 4. Lot No. _____ Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Huston K. Kennedy, in a field survey on December 2, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post; 10" Tamarack N50°W 28 Links; 10" Tamarack S34°E 15 Links
- 1.) 1975-Henderson, P.S. #16043; LCRC L.6432, Pg.370 - Fnd 1/2" Iron Pipe
- 2.) 1976-Kennedy, P.S. #17623; LCRC L.6821, Pg.466 - Fnd 1" Iron Pipe
- 3.) 1977-Buckerfield, P.S. #10868 L.6929, Pg.884 - Fnd 3/4" pinched top pipe in gravel shoulder
- 4.) 1975-Kennedy, P.S. #17623 L6717, Pg.295 - Fnd 1" Pipe, used same wit as 1976 LCRC

700
file

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1" Iron Rod 2.5' South of Lakeville Road, which has a bituminous surface and under a steel beam guard rail.

Witnesses from LCRC #1, 2 & 3 were used to recover and verify the location of the found 1" Iron Rod.

I accepted the found 1" Iron Rod as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

- M-9 to M-8 2852.15 Ft. (H. Kennedy 1977)
- M-9 to L-9 2465.61 Ft. (H. Kennedy 1977)
- M-9 to M-10 2479.38 Ft. (H. Kennedy 1977)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-9 I replaced the found 1" Iron Rod with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623.
- N19°E 43.77' Set PK & Remon. Washer NW face Power Pole
- S90°E 146.83' Set PK & Remon. Washer North face 25" Ash
- S82°E 140.50' Set PK & Remon. Washer NE face 21" Ash
- Due South 3.04' Set PK & Remon. Washer West face Guard Rail Post

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence position of the original corner.



Signed by [Signature]
Surveyor's Michigan License No. 17623

Date January 5, 1995