

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970, \$ 7.00 MISCELLANEOUS RECORDING

For corners in Oakland (County)

Located In: Oxford Twp.

Corner Code #

\$ 2.00 REMONUMENTATION
14 JUL 95 8:40 A.M. RECEIPT# 9B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Table with 3 columns: Description, T/R coordinates, and Corner Code #. Includes rows for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Section.

Compliance with ACT 345, P.A. 1990

APPROVED ON: 6-21-95 JDM/S
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, Huston K. Kennedy, in a field survey on April 26, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 2-13. Contains numbers 6 through 36.

A. Description of original monument and accessories and/or subsequent restoration:

- 1818-GLO Wampler, D.S.; Set Post 11" White Oak S30°W 54 Links; 17" Black Oak N51°E 42 Links
1.) 1974-Jones, PS #16045; LCRC L.6381, Pg.656 & 657 - Fnd 1" Iron
2.) 1991-Kennedy, PS #17623; LCRC L.11996, Pg.24 - Fnd 3/4" Iron Pipe
3.) 1989-Kennedy, PS #17623; Unrecorded Survey - Fnd 3/4" Iron Pipe, used same wit as 1991 LCRC
4.) 1991-Kennedy, PS #17623; Unrecorded Survey - Fnd 3/4" Iron Pipe, used same wit as 1991 LCRC
5.) 1994-Ward, PS #22445; Unrecorded LCRC - Set Concrete Monument w/2" diameter brass cap stamped Oakland County Remonumentatio PS #22445

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd Concrete Monument w/2" brass cap stamped Oakland County Remonumentation, #22445 3' East of the centerline of Barr Road extending to the North with a gravel surface, and 18' South of the centerline Indian Lake Road extending to the East & West with a gravel surface. A tree-fence row extending to the South. This corner is al being accepted and used as a common corner with the Northwest corner of Section 6, T4N, R11E, Oakland Twp. (A-1) and the Nort east corner of Section 1, T4N, R10E, Orion Twp. (M-1), also the Southwest corner of Section 30, T5N, R11E, Addison Twp. (A-13

Witnesses from LCRC # 1 & 2 were used to recover and verify the location of the found Concrete Monument w/2" brass cap stamp Oakland County Remonumentation, PS #22445.

I accepted the found Concrete Monument w/2" brass cap stamped Oakland County Remonumentation, PS #22445 as the best evidence the original corner position.

FIELD MEASUREMENTS BETWEEN

M-13 to L-13 2624.55 Ft., GLO = 40 chains or 2640.00 Ft. M-13 to M-12 2642.75 Ft., GLO = 40 chains or 2640.00 Ft.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-13 I found Concrete Monument w/2" diameter brass cap stamped Oakland County Remonumentation, PS #22445
N73°E 18.63' Fnd PK Nail & Brass Disc. #22445 North face 18" Elm
S10°E 24.45' Fnd PK Nail & Brass Disc. #22445 E face Utility Pole
N41°W 85.16' Fnd PK Nail & Brass Disc. #22445 SW face 6" Box Elder
N31°E 90.57' Fnd PK Nail & Brass Disc. #22445 SE face Utility Pole South 32.91' Found Concrete Monument

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best position of the original corner.

Signed by [Signature]
Surveyor's Michigan License No. 17623

Date June 15, 1995

