

**SURVEY &
REMONUMENTATION**

LIBER 14833 PG 155

94 193399

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in **COMMISSION**
Oakland
(County)

	Located In:		Corner Code #
	5N	11E	A-3
1. Public Land Survey	T _____ R _____	T _____ R _____	_____
	T _____ R _____	T _____ R _____	_____
	T _____ R _____	T _____ R _____	_____
	T _____ R _____	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	S _____ T _____ R _____	_____

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
15 JUL 94 7:38 A.M. RECEIPT# 1A
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
Compliance with
ACT 345, P.A. 1990

APPROVED ON: 1-19-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Bruce Antcliff, in a field survey on November 10, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-3 GLO Post	Survey L. 5905, P. 760	LC.R.C. L 8190 P. 67 (1982)	Survey L. 6702 P. 886 (1976)	Survey by P.E. Prangus (6/28/78)
	Found 1/2" Solid Iron Rod	Found 1/2" iron rod	Found 1/2" Iron Rod	1/2" Re Rod
	S 45° W 42.09' Tree	N 15° E - 28.95' 21" Oak	Fence Post NW - 43.34'	N 35° E 31.31' 24" Oak
	NE 30.93' 30" Oak	N 70° E - 30.59' 29" Oak	16" Oak NNE - 28.77'	S 24.63' Stump
	S 24.62' 28" Stump	S 70° W - 42.28' 22" Oak	18" Oak SW - 41.49'	S 55° W 42.13' 15" Oak
		S 30° E - 47.72' 12" Maple		

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-3 Found 1/2" iron bar at center line of Gravel Road E. - W. (Oakwood Road) and Tree Row South
Checks the following witnesses:

Survey L. 5905, P. 760	LC.R.C. L 8190 P. 67	Survey L. 6702 P. 886	Survey by P.E. Prangus
S 45° W 42.09' Tree	N 70° E - 30.59' 29" Oak	16" Oak NNE - 28.77'	S 55° W 42.13' 15" Oak
NE 30.93' 30" Oak	S 70° W - 42.28' 22" Oak	18" Oak SW - 41.49'	


Per GLO notes this corner is common with the SE corner of Section 1 T5N, R10E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-3 The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Set 5/8" rear and standard Oakland County cap.

- P.K. Nail and Brass Tag in E Face 22" Oak S 70° W - 41.41'
- P.K. Nail and Brass Tag in N Face 29" Oak N 70° E - 31.47'
- P.K. Nail and Brass Tag in SE Face Tri-10" Ash S 10° W - 42.12'
- P.K. Nail and Brass Tag in E Face 22" Oak N 20° E - 28.90'



Signed by Bruce Antcliff

Date 7-11-94

Surveyor's Michigan License No. 25826