

**SURVEY &  
REMONUMENTATION**

LIBER 14833 PG 154

94 193398

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE**

Compliance with  
ACT 345, P.A. 1990

Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED ON: 7-19-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

For corners in  
Oakland

**COMMISSION**

	Located In:		Corner Code #
	5N	11E	
1. Public Land Survey	T _____ R _____	_____	A-4
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
15 JUL 94 7:38 A.M. RECEIPT# 1A  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

OK - T. SMITH

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	

Bruce Antcliff

November 11

93

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19 \_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

A-4 GLO	L.C.R.C. L.7300 P. 668 (1978)	L.C.R.C. L.8096 P. 220 (1981)
No Corner Set	Found 1/2" iron rod	Found 1/2" Iron Rod
	S 40°W - 25.10' 6" Cherry	N 4.65' 12" Cherry
	S 24.74' 6" Cherry	S 30°W - 24.32' 6" Cherry
	N 4.78' 8" Cherry	S 17.09' 6" Cherry

Survey L. 7309, P. 655 (1978)  
Same Witness as  
L.C.R.C. L. 7300, P. 688

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

A-4 Found 1/2" iron bar at intersection of North, South, and East Fence Lines  
Checks the following witnesses:

L.C.R.C. L.7300 P. 668	Survey L. 7309, P. 655
S 40° W - 25.10 6" Cherry	S 40° W - 25.10 6" Cherry
S 24.74' 6" Cherry	S 24.74' 6" Cherry
N 4.78' 8" Cherry	N 4.78' 8" Cherry


Corner is being used as common with the E 1/4 corner of Section 12, T5N, R10E.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

A-4 The selected location of a corner, although not established by an original government survey, is accepted as the best available evidence of the position of the corner.

Set 4" concrete monument with standard Oakland County cap.

P.K. Nail and Brass Tag in W Face 24" Oak S 15° W - 32.31'  
P.K. Nail and Brass Tag in E Face 10" Cherry N 15° E - 25.54'  
P.K. Nail and Brass Tag in SE Face 10" Cherry N 60° E - 45.84'  
P.K. Nail and Brass Tag in N Face 10" Cherry East - 23.88'



Signed by Bruce Antcliff 25826  
Surveyor's Michigan License No. \_\_\_\_\_

Date 7-11-94