

**SURVEY &  
REMONUMENTATION**

LIBER **14833** PG **153**

**94 193397**

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Compliance with  
ACT 345, P.A. 1990

For corners in  
Oakland

**COMMISSION**

APPROVED ON: 7-19-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

	Located In:		Corner Code #
	5N	11E	
1. Public Land Survey	T ___ R ___	___	A-5
	T ___ R ___	___	___
	T ___ R ___	___	___
	T ___ R ___	___	___
2. Property Controlling in Section	S ___ T ___ R ___	___	___
	S ___ T ___ R ___	___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___	___
	S ___ T ___ R ___	___	___

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
15 JUL 94 7:37 A.M. RECEIPT# 1A  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS  
**OK - T. SMITH**  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Bruce Antcliff, in a field survey on November 9, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

A-5 GLO Post	L.C.R.C. L.6717 P. 294 (1976) Found 1/2" Iron Pin N 25° E - 30.21' 17" Cherry S 60° E - 50.69' 34" Oak South 24.92' Fence Corner	L.C.R.C. L.7300 P. 668 (1978) Found 1/2" Iron S 02° W - 27.64' 30" Oak S 47° W - 50.70' 42" Oak N 30° W - 30.26' 18" Cherry
--------------	--	---

Survey L. 7300, P. 655  
Same as L.C.R.C. L. 7300, P. 668

(Five Links North of the SE Corner, Section 12, T5N, R10W.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-5 Found 1/2" iron bar at center line of gravel roads running E - W (Noble Road) and fence line running South.  
Checks the following witnesses:

L.C.R.C. L.6717 P. 294 S 60°E - 50.69' 34" Oak Fence Corner Post S 24.92'	L.C.R.C. L.7300 P. 668 S 02°W - 27.72' 30" Oak S 47° W - 50.7' 42" Oak
---	--

Although the GLO notes show this corner as being 3.30' north of the SE corner, Section 12, T5N, R10W, it appears that it is being held as common.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-5 The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Set 5/8" rebar with standard Oakland County cap.

P.K. Nail and Brass Tag in NW Face P. Pole N 65°E - 87.89'  
P.K. Nail and Brass Tag in E Face 18" Ash N 07°W - 87.27'  
P.K. Nail and Brass Tag in SW Face 48" Oak S 47°E - 49.75'  
P.K. Nail and Brass Tag in NW Face 18" Cherry S 50°W - 24.63'



Signed by Bruce Antcliff  
Surveyor's Michigan License No. 25826

Date 7-11-94