

SURVEY &  
REMONUMENTATION

LIBER 15234 PG 522

FEB 29 01 99 69

OK - T. SMITH

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 \$ 7.00 MISCELLANEOUS RECORDING

For corners in **COMMISSION**

Located in:	Addison Township	Corner Code #
<u>Oakland</u> (County)		
1. Public Land Survey	T <u>5N</u> R <u>11E</u>	<u>A-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

\$ 2.00 REMONUMENTATION  
2 FEB 95 7:21 A.M. RECEIPT# 2B  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 11-30-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on November 16 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-7 Per G.L.O. notes, J. Wampler set a post in 1816 and 1817.

L.C.R.C. L. 6575 P. 114 1975 Wooden _____ N 60° E 27.52' 12" Oak S 10° E 29.43' 18" Maple S 80° W 31.94' 13" Ash	Kennedy Survey 1983 S 20° W 36.88' 15" Oak N 50° W 55.27' 8" Maple N 20° E 42.48'	L.C.R.C. L. 10709 P. 790 1988 S 20° W 36.88' 15" Oak N 50° W 55.27' 8" Maple N 20° E 42.48'	L.C.R.C. L. 12885 P. 257 1992 S 20° W 36.88' 15" Oak N 50° W 55.27' 8" Maple N 20° E 42.48' East 47.85' to 1/2" Iron Bar
--	--	--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7 Found 1/2" iron rod in swamp 2650' ± South of the NW corner of Section 18. Checks the following witnesses.

L.C.R.C. L. 6575 P. 114 S 80° W 32' to C/L Stump	Kennedy Survey 1983 S 35° W 36.37' P.K. & Tag #17623 E Side 20" Oak N 65° W 55.32' P.K. & Tag #17623 S Side Tw. 20" Maple N 25° E 42.52' P.K. & Tag #17623 SW Side 18" Oak	L.C.R.C. L. 12885 P. 257 1992 East 48.75' Rebar with Cap #10868
---	---	--

Kennedy Measures North 2658.58' to A-6  
Buckerfield Measures East 2659.25' to B-7

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7 Set a 5/8" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854" in place of found 1/2" iron bar.

- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in E Side 20" Oak S 35° W 36.37'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in S Side Tw. 10" Maple N 65° W 55.32'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SW Side 18" Oak N 25° E 42.52'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SE Side 10" W. Oak N 60° E 34.23'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" East 35.12'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" East 48.75'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J Kolehouse  
Surveyor's Michigan License No. 25854

Date 12/23/94

