

JUL 14 95 125229

LIBER 15517-397

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Oakland
(County)

Located in: Addison Twp. Corner Code #

1. Public Land Survey	T	5 N	R	11 E	A-8
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

\$ 7.00 MISCELLANEOUS RECORDING
 \$ 2.00 REMONUMENTATION
 14 JUL 95 8:55 A.M. RECEIPT# 88
 PAID RECORDED - OAKLAND COUNTY
 LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
 Compliance with
 ACT 345, P.A. 1990
 APPROVED ON: 6-21-95 JMS.
 OAKLAND COUNTY REMONUMENTATION
 PEER GROUP COMMITTEE
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Huston K. Kennedy, in a field survey on April 26, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 1818-GLO Wampler, D.S.; No post set
 1.) 1992-Buckerfield, PS #10868; LCRC L.12885, Pg.256 - Fnd 1/2" Iron Rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 3/8" Iron Rod with a fence line extending to the North, South & West. The corner is being accepted and used as a common corner with the East 1/4 corner of Section 24, T5N, R10E, Oxford Twp. (N-8)

Witnesses from LCRC #1 were used to recover and verify the location of the found 3/8" Iron Rod.

I accepted the found 3/8" Iron Rod as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

A-8 to A-7 2605.22 Ft., GLO not measured
 A-8 to A-9 2519.23 Ft., GLO not measured

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 A-8 I replaced the found 3/8" Iron Rod with 1/2 Iron Rod encased in a 4" diameter concrete cylinder 36" long w/2" diameter brass ca stamped Oakland County Remonumentation, PS #17623
 N03°W 9.17' Set PK & Remon. Washer West face 24" Oak
 N83°W 21.70' Set PK & Remon. Washer NE face 10" Oak
 S39°W 29.17' Set PK & Remon. Washer SE face 10" Oak
 S65°E 41.10' Set PK & Remon. Washer SW face 23" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]
 Surveyor's Michigan License No. 17623

Date June 15, 1995

