

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Oakland (County)

Located In: Addison Twp. Corner Code # A-9

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
14 JUL 95 8:35 A.M. RECEIPT# 88  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 6-21-95 Tom S.  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

- 1. Public Land Survey T 5 N R 11 E A-9  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	6	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	18	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Huston K. Kennedy, in a field survey on April 26, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1818-GLO Wampler, D.S.; Intersected the township line 10 links North of post; 12" Birch S30°W 87 Links; 10" Ash N32°E 42 Links. 1 recorded LCRC's, Certificate of Survey or Unrecorded Surveys were found for this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd with fence corner with a fence line extending to the East & North and was located in a pond with about 12" of the top of the fence corner sticking out of the water. The above is information taken from a Certificate of Survey dated January 25, 1977.

Based upon my surveying notes for the survey I made in January 25, 1977, the following was done to recover the corner:

- 1.) I set a point on a straight line between the East 1/4 corner and the Southeast corner of Section 24, T5N, R10E, Oxford Township, 332.25 feet North of the Southeast corner of said Section 24, I also checked to the next corner to the North (which is the Northwest corner of Job No. 76-786 also the A-9 is the Southwest corner of surveyed parcel) it checked within 0.30 feet. The difference in the distance between B-9 to A-9 is 0.74 feet (this difference could be due to the fact I measure the top of the fence corner in 1977 and I now am measuring to the corner on the township line).

FIELD MEASUREMENTS BETWEEN

A-9 to A-10 2796.95 Ft., GLO not measured A-9 to A-8 2519.23 Ft., GLO not measured A-9 to M-9 332.25 Ft., GLO = 10 links 6.60 Ft.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-9 I set a 1/2" x 60" Iron Pipe w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623
- N04°W 119.60' Set PK & Remon. Washer West face 32" Willow
- N17°E 97.82' Set PK & Remon. Washer NW face 8" Willow
- N22°W 195.09' Set PK & Remon. Washer SW face 17" Ash
- N25°W 166.80' Set PK & Remon. Washer SW face 6" Poplar

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best position of the original corner.

Signed by [Signature]  
Surveyor's Michigan License No. 17623

Date June 15, 1995

