

COPY

JUL 14 95 125231

LIBR 15517-399

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 \$ 7.00 MISCELLANEOUS RECORDING

For corners in Oakland (County)

Located In: Addison Twp. Corner Code #

\$ 2.00 REMONUMENTATION 14 JUL 95 8:35 A.M. RECEIPT# 88 PAID RECORDED - OAKLAND COUNTY LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Table with 4 columns: Item, T, R, A-10. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Section.

Compliance with ACT 345, P.A. 1990 APPROVED ON: 6-21-95 OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat Private Claims

Grid table with columns A-L and rows 1-13. Contains numbers 6-36.

I, Huston K. Kennedy, in a field survey on April 26, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1818-GLO Wampler, D.S.; No post set 1.) 1977-Buckerfield, PS #10868; LCRC L.6929, Pg.880 - Fnd 1/2" Iron Bar 2.) 1987-Kennedy, PS #17623; Unrecorded Survey - Fnd 1/2" Iron Rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 5/8" Iron Rod on the West side of a old road bed extending North & South with a tree-rock row extending to the East. The East 1/4 corner of Section, T5N, R10E, Oxford Twp. (M-10) is located 17.08 feet t the South.

Witnesses from LCRC #1 and Unrecorded Survey #2 were used to recover and verify the location of the found 5/8" Iron Rod.

I accepted the found 5/8" Iron Rod as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

- A-10 to A-9 2796.95 Ft., GLO not measured A-10 to A-11 2672.83 Ft., GLO not measured A-10 to M-10 16.24 Ft., GLO not measured

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-10 I replaced the found 5/8" Iron Rod with a 1/2" Iron Rod encased in a 4" diameter concrete cylinder w/2" diameter brass cap stampe Oakland County Remonumentation, PS #17623 N17° E 27.13' Set PK & Remon. Washer West face 14" & 17" Twin Oak N21° W 25.90' Set PK & Remon. Washer NE face 23" Oak S84° W 22.80' Set PK & Remon. Washer SE face 17" Hickory S40° E 31.25' Set PK & Remon. Washer NE face 25" Oak South 17.08 feet East 1/4 corner of Section 30, T5N, R10E, Oxford Twp. (M-10)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of position of the original corner.

Signed by [Signature] Surveyor's Michigan License No. 1623

Date June 15, 1995

