

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Oakland (County)

Located In: Addison Twp. Corner Code #

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
14 JUL 95 8:35 A.M. RECEIPT# 88
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990

APPROVED ON: 6-21-95 Toms
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

Table with 4 columns: Item, T, R, A-11. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Section.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Huston K. Kennedy, in a field survey on April 26, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-K and rows 2-13. Contains numbers 6 through 36.

A. Description of original monument and accessories and/or subsequent restoration:

- 1818-GLO Wampler, D.S.; Set Post 24" Black Oak S32°E 34 Links; 8" White Oak N33°W 30 Links
1.) 1972-Buckerfield, PS #10868; LCRC L.5892, Pg.251 - Fnd 1/2" Iron Bar
2.) 1973-Jones, PS #16045; LCRC; L.6124, Pg.218 - Fnd 1/2" Iron Rod
3.) 1987-Kennedy, PS #17623; Unrecorded Survey - Fnd 1/2" Iron Rod
4.) 1993-Kennedy, PS #17623; Unrecorded Survey - Fnd 1/2" Iron Rod, used same wit as Unrecorded Survey #3

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1/2" Iron Rod 6 feet South of the centerline of Drahner Road extending to th East & West, which has a gravel surface, 24 feet West of the centerline of Barr Road extending to the North, which has a grave surface, and 22 feet West of the driveway for house #1750. Found second 1/2" Iron Rod 16.30 feet West of corner. This corner i being accepted and used as a common corner with Sections 25 & 36, T5N, R10E, Oxford Twp. (A-11).

Witnesses from Unrecorded Surveys were used to recover and verify the location of the found 1/2" Iron Rod.

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

A-11 to A-12 2563.15 Ft., GLO not measured
A-11 to A-10 2672.83 Ft., GLO no measured

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-11 I replaced the found 1/2" Iron Rod with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation PS #17623
S11°E 18.12' Set PK & Remon. Washer NE face clump of Cherry
S63°W 26.15' Set PK & Remon. Washer NW face 22" Oak
N53°E 93.97' Set PK & Remon. Washer NW face Power Pole
N48°W 57.83' Set PK & Remon. Washer SW face 18" & 26" twin Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence position of the original corner.

Signed by [Signature]
Surveyor's Michigan License No. 17623

Date June 15, 1995

