

JUL 14 95 125233

LIBER 15517-401

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
14 JUL 95 8:35 A.M. RECEIPT# 88
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in Oakland (County)

Located In: Addison Twp Corner Code #

Table with 5 rows and 4 columns: 1. Public Land Survey, 2. Property Controlling in Section, 3. Miscellaneous Property in Section, 4. Lot No., 5. Private Claims. Columns include T/S, 5N, R, 11E, and A-12.

Compliance with ACT 345, P.A. 1990

APPROVED ON: 6-21-95 Tom S. OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 2-13. Contains numbers 1-36 in a grid pattern.

I, Huston K. Kennedy, in a field survey on April 26, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1818-GLO Wampler, D.S.; No post set
1.) 1980-Buckerfield, PS #10868; LCRC L.7777, Pg.373 - Fnd 1/2" Iron Bar
2.) 1984-Kennedy, PS #17623; LCRC L.8599, Pg.135 - Fnd 1/2" Iron Rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1/2" Iron Rod 4 feet West of the centerline of Barr Road extending to the North & South, which has a gravel surface, and 54 feet South of Cherokee Court extending to the East, which has a bituminous surface. This corner is being accepted and used as a common corner with the East 1/4 corner of Section 36, T5N, R10E, Oxford Twp. (M-12).

Witnesses from LCRC #1 & 2 were used to recover and verify the location of the found

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

- A-12 to A-13 2642.75 Ft., GLO not measured
A-12 to A-11 2563.15 Ft., GLO not measured

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-12 I replaced the found 1/2" Iron Rod with a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #17623
N20°W 58.10' Set PK & Remon. Washer East face 18" Oak
N79°W 84.55' Set PK & Remon. Washer North face 13" Oak
S67°W 29.69' Set PK & Remon. Washer NW face 19" Walnut
S27°E 67.13' Set PK & Remon. Washer SW face 22" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best evidence of the position of the original corner.

Signed by [Signature]
Surveyor's Michigan License No. 17623

Date June 15, 1995

