

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION

For corners in Oakland  
(County)

Located In: Addison Twp. Corner Code #

14 JUL 95 8:36 A.M. RECEIPT# 88  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

1. Public Land Survey	T	<u>5N</u>	R	<u>11E</u>	<u>A-13</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		R
	S		T		R
3. Miscellaneous Property in Section	S		T		R
	S		T		R

Compliance with ACT 345, P.A. 1990

APPROVED ON: 6-21-95 Tom S.  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Huston K. Kennedy in a field survey on April 26, 19 95 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

1818-GLO Wampler, D.S.; Set Post 10" White Oak S30°W 54 Links; 17" Black Oak N51°E 42 Links

- 1.) 1978-Buckerfield, PS #10868; LCRC L.7152, Pg.137 - Fnd 3/4" Pipe
- 2.) 1984-Kennedy, PS #17623; LCRC L.8599, Pg.135 - Fnd 1" Iron Pipe
- 3.) 1994-Ward, PS #22445; Unrecorded LCRC - Set 4" Concrete Monument w/2" diameter brass cap stamped Oakland County Remonumentation PS #22445

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd Concrete Monument w/2" brass cap stamped Oakland County Remonumentation, PS #22445 3' East of the centerline of Barr Road extending to the North with a gravel surface, and 18' South of the centerline of Indian Lake Road extending to the East & West with a gravel surface. A tree-fence row extending to the South. This corner is also being accepted and used as a common corner with the Southeast corner of Section 36, T5N, R10E, Oxford Twp. (M-13), also the North west corner of Section 6, T4N, R11E, Oakland Twp. (A-1) and the Northeast corner of Section 1, T4N, R10E, Orion Twp. (M-1).

Witnesses from LCRC #1 and Unrecorded Survey #3 were used to recover and verify the location of the found Concrete Monument w/2 brass cap stamped Oakland County Remonumentation, PS #22445.

I accepted the found Concrete Monument w/2" brass cap stamped Oakland County Remonumentation, PS #22445. as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

A-13 to A-12 2642.75 Ft., GLO not measured A-13 to M-12 (Oxford Twp.) 2624.75 Ft., GLO = 40 chains or 2640.00 Ft.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13 I found a 4" diameter Concrete Monument w/2" diameter brass cap stamped Oakland County Remonumentation, PS #22445  
N73°E 18.63' Fnd PK Nail & Brass Disc. #22445 North face 18" Elm S10°E 24.45' Set PK Nail & Brass Disc. #22445 E face Utility Pol  
N41°W 85.16' Fnd PK Nail & Brass Disc. #22445 SW face 6" Box Elder  
N31°E 90.57' Fnd PK Nail & Brass Disc. #22445 SE face Utility Pole  
South 32.91' Found Concrete Monument

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]

Date June 15, 1995

Surveyor's Michigan License No. 17623

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS  
HUSTON KENNEDY  
PROFESSIONAL SURVEYOR  
17623