

SURVEY & REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Compliance with ACT 345, P.A. 1959 24 193394

MAY - 1 1995

Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED ON: 1-19-94 OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE

For corners in Oakland (County)

COMMISSION

Located In:

Corner Code -#

Table with 3 columns: Description, Located In (5N, 11E), and Corner Code (#). Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number: \$ 7.00 MISCELLANEOUS RECORDING \$ 2.00 REMONUMENTATION 15 JUL 94 7:37 A.M. RECEIPT# 1A PAID RECORDED - OAKLAND COUNTY LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

4. Lot No. , Recorded Plat 5. Private Claims

Grid table with columns A-L and rows 1-13. A dot is marked in cell C2.

Bruce Antcliff November 10 93

I, Bruce Antcliff, in a field survey on November 10, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: C-1 GLO L.C.R.C. L6379 P. 287 (1974) Found 1" Iron Pipe N 70° E - 4.68' 6" Ash N 40° W - 44.64' 21" Ash N 80° W - 63.74 19" Ash L.C.R.C. L7719 P. 716 (1979) Found 1" Iron Pipe N 35° W - 44.44' 10" Oak S 85° E - 26.3' 10" Oak N 35° W - 55.9' 12" Maple

Survey L.6989 P. 249 Pinch Pipe N 35° E - 4.69' 14" Tree S 85° E - 3.47' 10" "Popple" N 15° W - 4.87' F. Post

Survey H. Kennedy (3/21/89) Fnd Pinched Pipe S 5° W 2.90' PK/W West Face 5" Ash N 50° E 4.78' PK/W N. Face 15" Ash Due East 3.45' PK/W South Face 9" Ash

Handwritten signature/initials.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: C-1 Found 1" pinch pipe 5' South of corner fence post (fence running E). Checks the following witnesses:

L.C.R.C.L. 6379, P. 287 N 70°E - 4.68' 6" Ash

Survey L.C.R.C. L. 6989, P. 249 N 15° W - 4.87 Fence Post

Survey H. Kennedy (3/21/89) S 5° W 2.90' PK/W West Face 5" Ash N 50° E 4.78' PK/W N. Face 15" Ash

The GLO notes show this corner to be 3.30' East of SE corner Section 31, T6N, R11. No evidence of said corner (Survey L.7719 P. 712 shows SE corner Section 31 to be 723.1 East???)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: C-1 The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Set concrete monument with standard Oakland County cap.

- P.K. Nail and Brass Tag in SW Face Twin 20" Ash S 16° E - 61.35' P.K. Nail and Brass Tag in S Face 20" Oak N 80° W - 60.33' P.K. Nail and Brass Tag in E Face 12" Oak S 45° W - 43.99' P.K. Nail and Brass Tag in S Face 18" Ash N 80° E - 22.54'



Signed by Bruce Antcliff 25826 Surveyor's Michigan License No.

Date 7-11-94