

**SURVEY &
REMONUMENTATION**

FEB 295019966

MAY - 1 1995

LIBER 15234 PC 519

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in

COMMISSION

<u>Oakland</u> (County)	Located in:	Addison Township	Corner Code #
1. Public Land Survey	T <u>5N</u>	R <u>11E</u>	<u>C-6</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
2 FEB 95 7:20 A.M. RECEIPT 28
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 11-30-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kolehouse, in a field survey on July 27 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-6 Per G.L.O. notes, J. Wampler set a post in 1817.

O.C.R.C. Iron 1933 24" Oak NW 24.8 15" Oak NE 35.2'	O.C.R.C. 1962 1" x 18" Iron 24" Oak NW 24.5' 15" Oak NE 35.2'	L.C.R.C. L. 5878 P. 648 1971 Set 3/4" Pipe Projecting 1.8 ft. NW 38.0' SE Face 18" Oak W 62.43' Nail in N Face Twin 10" Maple SW 49.3' Nail in Face 14" Maple	L.C.R.C. L. 6123 P. 554 1973 N 45° W 22.55' 6" Maple S 35° W 18.70' 6" Box Elder
---	--	---	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-6 Found 3/4" iron pipe projecting 1.8' ± 30' East of C/L gravel two track running N-S and ± 30' West of West end of a crumbling stone wall running East. Also found 1/2" iron bar .15' West and checked following witnesses.

L.C.R.C. L. 5878-648 1971
NW 37.90' Nail in SE Side of 20' Oak
W 62.42' Nail in N Side of N Twin 10" Maple Stump
SW 49.27' Nail in N Side 16" Maple

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-6 Set a 4" x 36" concrete monument with brass cap stamped "Oakland County Remonumentation P.S. #25854" in place of found 3/4" pipe.

- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NW Side 18" Ash S 67° W 18.56'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NW Side Quad 6" Ash S 18° W 9.44
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in S Side 12 Ash S 68° E 9.43'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SE Side 20" Oak N 35° W 37.90'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in N Side N. Stump 10" Maple W 62.42'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in N Side 16" Maple S 73° W 49.27'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/23/94
Surveyor's Michigan License No. 25854

