

MAY - 1 1995

LIBER 15234 pg 524

OK - T. SMITH

LAND CORNER RECORDATION CERTIFICATE COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Table with columns: Located in: Addison Township, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

7.00 MISCELLANEOUS RECORDING \$ 2.00 REMONUMENTATION 2 FEB 95 7:21 A.M. RECEIPT# 28 PAID RECORDED - OAKLAND COUNTY LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990 APPROVED ON: 11-30-94 OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, Randy Kolehouse, in a field survey on September 20 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-8 Per G.L.O. notes, J. Wampler set a post in 1817.

Table listing survey details: O.C.R.C. 1962, L.C.R.C. L. 8010 P. 826 1981, L.C.R.C. L. 8190 P. 67, Cert. Survey 1988. Includes monument types like Iron Pipe, Tree, Post, Pole and bearings/distances.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-8 Found a 1/2" rebar 3' West of the West edge of Hosner Road running N-S which checks the following witnesses.

Table listing survey details for corner B: L.C.R.C. L. 8010 P. 826 1981, L.C.R.C. L. 8190 P. 67, Cert. Survey 1988. Includes bearings/distances and monument types like Oak, Pole, Iron, Ash.

This corner also checks the following Cert. Surveys: L. 8026 P. 534 (1981), L. 7326 P. 618 (1978), and is shown in several Certified Surveys by Kennedy Surveying.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-8 Set a 5/8" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854" in place of found 1/2" iron.

- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in N Side P. Pole N 75° W 56.95'
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NE Side 24" Oak S 30° W 26.48'
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in W side 24" Oak S 50° E 42.65'
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NW Side 50" Oak N 32° E 49.77'
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in W Side 18" Ash South 39.79'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/23/94 Surveyor's Michigan License No. 25854

