

**SURVEY &
REMONUMENTATION**

MAY - 1 1995

LIBER **14833** PG **145**

94 193389

Compliance with
ACT 345, P.A. 1990

LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED ON: 1-19-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

For corners in
Oakland

(County)	Located In:	Corner Code #
	5N 11E	D-3
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
15 JUL 94 7:32 A.M. RECEIPT# 1A
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

OK - T. SMITH

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3			●									
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Bruce Antcliff, in a field survey on November 11, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-3	GLO Post	Survey: Air Land Surveys, Inc. Found 1/2" Iron N 10° W 36.08' PK in S Face HBT Pole S 80° E 93.79' PK in N Face 16" Oak S 45° E 31.10' PK in NW Face 16" Oak S 50° W 39.92' PK in NE Face 18" Ash	L.C.R.C. L.5971 P. 21 (1972) 1/2" iron pipe S 65° E - 92.85' 14" Oak S 65° W - 41.87' 16" Ash S 50° E - 31.80' 16" Oak	Survey L. 6383, P. 886 & L.C.R.C. L.7288 P. 544 (1978) found iron pipe S 50° E - 31.19' 16" Oak N 80° E - 106.11' 26" Oak S 80° W - 41.97' 16" Ash
-----	-------------	--	--	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-3 Found 1/2" iron bar at E of gravel road E & W (Oakwood Road) and fence line South.

Checks the following witnesses:


Survey: Air Land Surveys, Inc. S 45° E 31.10' PK in NW Face 16" Oak N 10° W 36.08' PK in S Face T Pole S 80° E 93.79' PK in N Face 16" Oak	L.C.R.C. L.5971 P. 21 S 50° E - 31.80' 16" Oak	Survey L. 6383, P. 886 & L.C.R.C. L.7288 P. 544 (1978) N 80° E - 106.11' 26" Oak S 80° W - 41.97' 16" Ash S 50° E - 31.80' 16" Oak
---	---	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-3 The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Set 5/8" rebar with standard Oakland County cap.

- P.K. Nail and Brass Tag in NW Face 14" Ash N 60° E - 42.44'
- P.K. Nail and Brass Tag in SW Face 22" Oak S 74° E - 93.63'
- P.K. Nail and Brass Tag in NW Face 20" Ash S 80° W - 40.26'
- P.K. Nail and Brass Tag in SW Face Twin 10" Box Elder N 15° W - 39.6'



Signed by Bruce Antcliff
Surveyor's Michigan License No. 25826

Date 7-11-94