

SURVEY &
REMONUMENTATION

LIBER 15234 PC 527

FEB 29 50 1997

MAY - 1 1995

OK - T. SMITH

LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970 \$ 7.00 MISCELLANEOUS RECORDING

For corners in

<u>Oakland</u> (County)	Located in: Addison Township	Corner Code # D-9
1. Public Land Survey	T <u>5N</u> R <u>11E</u>	<u>D-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

\$ 2.00 REMONUMENTATION
2 FEB 95 7:22 A.M. RECEIPT# 2B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 11-30-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kolehouse, in a field survey on July 27 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-9 Per G.L.O. notes, J. Wampler set a post in 1817.

O.C.R.C. 1956 NNE 31.10' E Side 16" Elm N 33.15' S Face Wood Cor. Post WNW 52.40' SW Side 8" Oak SW 50.48' NW Side D.E. Pole	L.C.R.C. L. 5892 P. 267 1972 1/2" Iron Bar N 70° W 52.71' 12" Oak North 32.52' Tel. Pole S 40° W 50.46' Tel. Pole	L.C.R.C. L. 7288 P. 544 1978 PK Nail N 70° W 52.60 14" Oak S 60° W 50.32' P. Pole North 32.54' P. Pole	Reichert Survey 1987 S 80° E 140.30' N Side P. Pole N 70° W 52.60 14" Oak S 60° W 50.32' P. Pole N 32.54' P. Pole
--	---	--	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-9 Found 1/2" iron bar in C/L of Lakeville Road (asphalt) running E-W. Checked the following witnesses.

O.C.R.C. 1956 WNW 12" Oak 52.7' SW D.E. Pole 50.48'	L.C.R.C. L. 5892-P. 267 N 57° W 52.70' Nail SW Side 18" Oak S 54° W 50.47' Nail & Washer SE Side D.E. Pole
---	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-9 Set a 5/8" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854" in place of found 1/2" iron bar. Also set monument box.

- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in S Side 16" Hickory S 79° W 100.61
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SW Side Twin 9" Box Alder N 60° E 57.72
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SW Side 18" Oak N 57° W 52.70'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SE Side D.E. Pole S 54° W 50.47'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/23/94
Surveyor's Michigan License No. 25854

