

MAY 16 1996

LIBER 15963 PG 374

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

\$ 7.00 MISCELLANEOUS RECORDING \$ 2.00 REMONUMENTATION

19 JAN 96 2:19 P.M. RECEIPT# 246A PAID RECORDED - OAKLAND COUNTY LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in

Table with columns: County (Oakland), Located in: Addison Township, Corner Code # (D-13), and survey details for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Compliance with ACT 345, P.A. 1990 APPROVED ON: 6-26-95 T.S. OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat Private Claims

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

I, Randy Kolehouse, in a field survey on December 27 19 95, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-13 1817 Wampler G.L.O. Set Post 1960 MDNR 1" Pipe 1995 Ward O.C.R. Dossiers D-1 T4N R11E Oakland Township Set Monument

This corner is common with D-1, T4N, R11E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13 Found a 4" concrete monument with 2" O.C. Remon. Cap #22445 23' South of a fence running East and West and 22' North of a fence corner of a fence running East and South.

Handwritten notes: 7.00, 2.00, 26

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 4" concrete monument with brass cap stamped "Oakland County Remonumentation P.S. #22445." As approved by O.C.R. Peer Group:

- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #22445" in SE Face 14" Oak N 45° E 23.71' PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #22445" in W Face 16" Oak S 5° E 22.68' PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #22445" in NW Face 16" Oak S 35° W 36.83' PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #22445" in SW Face 16" Oak N 60° W 28.99' Found Rebar on E/W/S Fence Line North 21.41'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.



Signed by Randy J. Kolehouse Date 12/27/95 Surveyor's Michigan License No. 25854