

**SURVEY &  
REMONUMENTATION**

MAY - 1 1995

LIBER 15234 PG 529

295019976

OK - T. SMITH

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970 \$ 7.00 MISCELLANEOUS RECORDING

For corners in

<u>Oakland</u> (County)	Located in:	Addison Township	Corner Code # E-8
1. Public Land Survey	T <u>5N</u>	R <u>11E</u>	<u>E-8</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

\$ 2.00 REMONUMENTATION  
2 FEB 95 7:22 A.M. RECEIPT# 28  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with  
ACT 346, P.A. 1990

APPROVED ON: 11-30-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on July 19 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

E-8 Per G.L.O. notes, J. Wampler set a post in 1817.

L.C.R.C. L. 6113 P. 125 1973  
Set R.R. Spike  
S 40° W 42.66' 20" Oak  
S 30° 42.60' 12" Maple  
N 30° E 77.07' 12" Locust

L.C.R.C. L. 7524 P. 756 1979  
R.R. Spike  
S 40° W 42.66' 22" Oak  
S 30° 42.60' 12" Maple  
N 30° E 77.07' 15" Willow

L.C.R.C. L. 10709 P. 795 1988  
Spike  
S 40° E 42.65' PK/W SW Side 19" Maple  
S 40° W 72.80' PK/W E Side 10" Oak  
S 60° W 42.85' PK/W NW Side 24" Oak

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-8 Found spike 3' East of the C/L of Lake George Road (gravel) running N-S and checked witnesses as follows:

L.C.R.C. L. 7524 P. 756 1979  
S 40° W 42.66' 22" Oak  
S 30° 42.60' 12" Maple  
N 30° E 77.07' 15" Willow

L.C.R.C. L. 10709 P. 795 1988  
S 40° E 42.68' PK & Washer SW Side 19" Maple  
S 40° W 72.82' PK & Washer E Side 10" Oak  
S 60° W 42.85' PK & Washer NW Side 24" Oak

Baldwin Measures South to E-9 2842.63'  
Kennedy Measures North to E-7 2496.18'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-8 Set a 5/8" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854" in place of found spike.

"X" Cut in Top of E. Conc. Bridge Wall N 13° E 63.87'  
"X" Cut in Top of W. Conc. Bridge Wall N 15° W 6596'  
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SW Side 19" Maple S 40° E 42.68'  
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in E Side 10" Oak S 40° W 72.82'  
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NW Side 24" Oak S 60° W 42.85'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy Kolehouse Date 12/23/94  
Surveyor's Michigan License No. 25854

