

**SURVEY &
REMONUMENTATION**

LIBER **15234** PC **531**

FEB 295019978

MAY - 1 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE \$ 7.00 MISCELLANEOUS RECORDING
Filing Requirement of Act 74, Mich. P.A. 1970 \$ 2.00 REMONUMENTATION

For corners in

	Located in:	Addison Township	Corner Code #
<u>Oakland</u> (County)			
1. Public Land Survey	T <u>5N</u> R <u>11E</u>		<u>F-9</u>
	T _____ R _____		_____
	T _____ R _____		_____
	T _____ R _____		_____
2. Property Controlling in Section	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____

2 FEB 95 7:22 A.M. RECEIPT# 28
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
OK - T. SMITH

Compliance with
ACT 345, P.A. 1990

APPROVED ON: 11-30-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kolehouse, in a field survey on July 27 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-9 Per G.L.O. notes, J. Wampler set a post in 1817.

O.C.R.C. 1967	L.C.R.C. L. 6124 P. 219 1973	L.C.R.C. L. 7353 P. 583 1978	L.C.R.C. L. 12773 P. 521
NW 36.24' Nail & Washer MBT	N 40° E 90.40' Guy Pole	5/8" Iron Bar	N 80° E 90.68' N/W N. Face P. Pole
NE 90.45' Nail & Washer in D.E. Guy	S 45° E 65.92' D.E. Pole	NE 90.60' Nail & Tag in Guy Pole	S 65° E 66.10' N/W N Face P. Pole
SE 65.97' Nail & Washer in D.E. Pole	South 33.00' Iron	SE 66.00' Nail & Tag in P. Pole	S 50° W 56.03' N/W SE Face P. Pole
		South 33.00' 1/2" Iron Bar	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-9 Found 1/2" iron bar in C/L Lakeville Road (gravel) running E-W 30' West of C/L Curtis Road and checked witnesses.

O.C.R.C.	L.C.R.C. L. 6124 P. 219 1973
N 22° W 36.78' P.K. in NE Side P. Pole	South 32.93' 1/2" Rebar
N 68° E 90.62' Nail & Tag in NW Side P. Pole	
S 63° E 66.06' Nail & Tag in NE Side P. Pole	

Baldwin Measures North to E-8 2842.63'
Baldwin Measures South to E-11 5266.43'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-9 Set a 5/8" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854" in place of found 1/2" iron rod. Also set monument box.

- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NW Side P. Pole S 68° W 99.85'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NE Side P. Pole N 22° W 36.78'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NW Side P. Pole N 68° E 90.62'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NE Side P. Pole S 63° E 66.06'
- 1/2" Rebar South 32.93'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy Kolehouse Date 12/23/94
Surveyor's Michigan License No. 25854

