

**SURVEY &  
REMONUMENTATION**

94 193380

MAY - 1 1995

LIBER 14833 PG 136

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Oakland

**COMMISSION**

OK - T. SMITH

(County)	Located In:	Corner Code #
	5N 11E	G-1
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
15 JUL 94 7:31 A.M. RECEIPT# 1A  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS  
ACT 345, P.A. 1990

APPROVED ON: 12-15-93  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Bruce Antcliff November 9 93  
I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19 \_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- |                          |                                 |                                  |
|--------------------------|---------------------------------|----------------------------------|
| G-1 GLO County Witness   | L.C.R.C. L. 5849, P. 478 (1972) | L.C.R.C. L. 6279, P. 705 (1974)  |
| Post Iron Pipe           | 1/2" Iron Bar                   | 1/2" Iron Rod                    |
| West - 21.8' Nail 24"    | NE - 52.84' N/W, 10" Oak        | N 25° E - 52.85' 10" Oak         |
| SE - 53.25' Nail 12" Oak | West 21.48' N/W, 48" Oak        | S 70° E - 28.74' 14" Oak         |
|                          | SE - 28.71' N/W, 14" Oak        | West 21.52' 38" Oak              |
|                          | East - 32.97' Iron Bar          |                                  |
|                          |                                 | Survey L. 6279, P. 794 (1974)    |
|                          |                                 | 1/2" Iron                        |
|                          |                                 | Same as L.C.R.C. L. 6279, P. 705 |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-1 Found 1/2" rebar ± 7' West of west edge of gravel road (Haven Road).  
Checks the following witnesses:


County Witness	L.C.R.C. L. 5849, P. 478	L.C.R.C. L. 6279, P. 705
West 21.8 24" Oak	Nail and Tag in 48" Oak - West - 21.48'	S 70° E - 28.74' 14" Oak
	Nail and Tag in 14" Oak - SE - 28.71'	West - 21.52' 38" Oak

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1 The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Set 5/8" rebar with standard Oakland County cap.

- P.K. Nail and Brass Tag in N Face 48" Oak - N 80° W - 21.97'
- P.K. Nail and Brass Tag in E Face 14" Oak - N 35° E - 52.90'
- P.K. Nail and Brass Tag in S Face 14" Oak - S 65° E - 28.32'
- P.K. Nail and Brass Tag in SW Face 12" Oak - S 10° E - 75.10'



Signed by Bruce Antcliff  
25826

Date 7-11-94

Surveyor's Michigan License No. \_\_\_\_\_