

SURVEY & REMONUMENTATION

LIBER 14833 PG 109

94 193353
OK - T. SMITH

Land/Co

MAY - 1 1995

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Oakland

(County)	Located In:		Corner Code #
	5N	11E	H-1
1. Public Land Survey	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
15 JUL 94 7:26 A.M. RECEIPT# 1A
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
Compliance with
ACT 345, P.A. 1990

APPROVED ON: *12-22-93* *LS*
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Bruce Antcliff November 93

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-1 GLO Post
L.C.R.C. L. 5849, P. 476 (1972)
North - 9.56' P.K./W in 6" Oak
East - 16.00' P.K./W in 18" Oak
West - 76.94' Concrete Monument

Handwritten signature

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-1 Found 1/2" Iron 77.00' East of Concrete Monment.
Checks the following witnesses:

P.K. Nail 18" Oak E - 15.82'
Concrete Monument W - 77.00'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-1 The selected location of a corner, although not established by an original government survey, is accepted as the best available evidence of the position of the corner.

Set concrete monument with standard Oakland County cap.

P.K. Nail and Brass Tag in E Face 24" Oak - North - 39.46'
P.K. Nail and Brass Tag in W Face 20" Oak - N 60° E - 24.84'
P.K. Nail and Brass Tag in W Face 16" Cherry - South - 27.24'
P.K. Nail and Brass Tag in S Face 6" Poplar - S 70° W - 31.84'



Signed by *Bruce Antcliff*
25826

Date *7-11-94*

Surveyor's Michigan License No. _____