

SURVEY & REMONUMENTATION

MAY 16 1996

LISER 15913 PC 755

Compliance with ACT 345, P.A. 1990

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED ON: 6-19-95 TS
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
29 DEC 95 9:02 A.M. RECEIPT# 448
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

22985259068

For corners in

<u>Oakland</u> (County)	Located in:	Addison Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11E</u>		<u>H-13</u>
	T _____ R _____		_____
	T _____ R _____		_____
	T _____ R _____		_____
2. Property Controlling in Section	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on May 31 19 95, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-13 1817 Wampler G.L.O. Set Post
1993 Ward L.C.R.C. L. 15095 P. 028 Set Iron Rod & Brass Cap #22445

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 Found 2" brass cap "Oakland County Remonumentation #22445" on an iron in a monument box 3.5' ± South of the C/L of Romeo Road (asphalt). There is a fence to the South. No occupation to the North and Tax Records for parcel in Addison Township is the S 1/2 of Sec. 34 Exc. NE 1/4 of the SE 1/4 of Sec. 34. Corner will be held as common to Oakland Township H-1 T4N R11E.

Measured E to I-13 = 2639.39' (G.L.O. = 2640')
Measured W to G-13 = 2646.86' (G.L.O. = 2640')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 4" concrete monument with brass cap stamped "Oakland County Remonumentation P.S. #22445."

PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #22445" in W Face 18" Oak N 30° E 48.35'
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #22445" in SE Face 16" Oak N 60° E 59.27'
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #22445" in SW Face 16" Poplar N 35° W 54.74'
Capped Iron (# Unreadable) S 5° W 32.81'



The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/22/95
EARTH TECH
Surveyor's Michigan License No. 25854

7.00
2.00
file