

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970


For corners in Oakland

OK - T. SMITH

(County)	Located In:	Corner Code #
1. Public Land Survey	5N 11E	I-2
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

\$ 7.00 MISCELLANEOUS RECORDING
 \$ 2.00 REMONUMENTATION
 15 JUL 94 7:26 A.M. RECEIPT# 1A
 PAID RECORDED - OAKLAND COUNTY
 LYNN D. ALLEN, CLERK REGISTER OF DEEDS
 Compliance with ACT 74, P.A. 1970
 APPROVED ON: 7-2-94
 OAKLAND COUNTY REMONUMENTATION
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____



Bruce Antcliff November 9 93
 I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-2	GLO Post	L.C.R.C. L. 6196, P. 458 (1972) 3/4" Iron Pipe N 88° W - 28.13' Nail N Side 36" Oak N 44° W - 44.00' Nail SW Side 24" Oak N 30° E - 53.66' Nail W Side 18" Maple	L.C.R.C. L. 11792, P. 229 (1991) Find 1/2" Pipe with Spike in Center NE - 52.50' P.K. Nail & Cap #17623 20" Maple SE - 31.34' P.K. Nail & Cap #17623 18" Elm W - 27.65' P.K. Nail & Cap #17623 48" Oak NE - 43.96' P.K. Nail & Cap #17623 26" Oak
-----	----------	--	--

Survey L 1179, P. 231 (1990)
 Same as L.C.R.C. L. 11792, P. 229

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-2 Found 1/2" Iron pipe with spikes in center in monument box at centerline of Rochester Road.
 Checks the following witnesses:

L.C.R.C. 6199, P. 458 N 44° W - 44.00' Nail in SW Side 24" Oak N 30° E - 53.66 Nail in W Side 18" Oak	L.C.R.C. L. 11792, P. 229 SE - 31.34' P.K. Nail & Cap # 17623 18" Elm NE - 43.96' P.K. Nail & Cap # 17623 26" Elm
---	---


Survey L 1179, P. 231 (1990)
 Same as L.C.R.C. L. 11792, P. 229

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-2 The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Set 5/8" rebar with standard Oakland County cap.

P.K. Nail and Brass Tag in W Face 20" Maple - N 35° E - 52.78'
 P.K. Nail and Brass Tag in N Face 16" Elm - S 50° E - 31.14'
 P.K. Nail and Brass Tag in E Face 24" Oak - N 40° W - 44.63'
 P.K. Nail and Brass Tag in E Face 6" Maple - S 30° W - 59.77'



Signed by Bruce Antcliff 25826
 Surveyor's Michigan License No. _____

Date 7-11-94