

SURVEY &  
REMONUMENTATION

94 193361

*Land 10*

LISER 14833 PG 117

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

\$ 7.00 MISCELLANEOUS RECORDING

\$ 2.00 REMONUMENTATION

15 JUL 94 7:28 A.M. RECEIPT 1A  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in  
Oakland

COMMISSION

(County)	Located In:		Corner Code #
	5N	11E	
1. Public Land Survey	T ___ R ___	___	I-6
	T ___ R ___	___	
	T ___ R ___	___	
	T ___ R ___	___	
2. Property Controlling in Section	S ___ T ___ R ___	___	
	S ___ T ___ R ___	___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___	
	S ___ T ___ R ___	___	

OK - T. SMITH

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 2-2-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Bruce Antcliff

November 12

93

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	N
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

I-6	GLO Post	County Witness	L.C.R.C. L. 5330, P. 563 (1971) 1/2" Iron	L.C.R.C. L. 6631, P. 838 (1975) 1/2" iron rod
		SW - 54.30' Nail 12" Oak	SW - 54.21' P.K. in 24" Oak	NW - 45.88' Concrete Monument
		SSW - 64.7' Nail 15" Oak	NW - 53.36' P.K. in P. Pole	ESE - 58.56' P.K. Nail 6" Spruce
		East - 26.9' Nail 12" Oak	NE - 39.21' P.K. in P. Pole	SW - 54.38' P.K. Nail 30" Oak

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-6 Reset 1/2" iron rod ± 2' W of centerline of Rochester Road and intersections of Rowland and Rochester Roads.  
Checks the following witnesses:

SW 54.3 Nail 30' Oak	L.C.R.C. L. 5330, P. 563 SW - 54.21' P.K. in 24" Oak NE - 39.21' P.K. in P. Pole	L.C.R.C. L. 6631, P. 838 SW - 54.38' P.K. 30" Oak
----------------------	--	--

*[Handwritten signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-6 The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Set 5/8" rebar with standard Oakland County cap and monument box.

- P.K. Nail and Brass Tag in E Face 32" Oak - S 37° W - 54.38'
- P.K. Nail and Brass Tag in SE Face 24" Oak - S 75° W - 54.40'
- P.K. Nail and Brass Tag in NE Face P. Pole - N 47° W - 50.31'
- P.K. Nail and Brass Tag in NW Face P. Pole - N 73° E - 39.04'



Signed by Bruce Antcliff  
Surveyor's Michigan License No. 25826

Date 7-11-94