

**SURVEY &
REMONUMENTATION**

FEB 29 501998

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

15234-534

For corners in **COMMISSION**

For corners in	Located in:	Addison Township	Corner Code #
<u>Oakland</u> (County)			
1. Public Land Survey	T <u>5N</u> R <u>11E</u>		<u>I-9</u>
	T _____ R _____		_____
	T _____ R _____		_____
	T _____ R _____		_____
2. Property Controlling in Section	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
2 FEB 95 7:23 A.M. RECEIPT# 28
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with
ACT 345, P.A. 1990
APPROVED ON: 12-12-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on July 28 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-9 Per G.L.O. notes, J. Wampler set a post in 1817.

O.C.R.C. Iron Pipe NE 68.90' Spike in 24" Oak SE 69.25' Spike in 15" Oak NNW 35.03' Spike in 24" Oak	L.C.R.C. L. 7417 P. 489 1978 N 80° E 68.48' 28" Oak S 60° E 69.00' 24" Oak W 34.85' 39" Oak	Record Survey L. 10304 P. 081 1988 3/8" Bar W 33.0' to Conc. Mon. S 45° E 55.58' to MBT Riser N 20° E 68.44' Nail & Tag 38" Oak	L.C.R.C. L. 12560 P. 595 1992 1/4" Iron Rod N 48° E 52.43' PK & Tag NW Side 10" Locust N 73° E 67.95' PK & Tag NW Side 28" Oak W 35.23' PK & Tag
------------------------------------------------------------------------------------------------------------------	------------------------------------------------------------------------------------------------------	---------------------------------------------------------------------------------------------------------------------------------------------	--------------------------------------------------------------------------------------------------------------------------------------------------------------

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-9 Found 1/2" iron rod over a 3/4" iron pipe (18" long) 3' East of the C/L of Rochester Road (asphalt) running N-S and 6' North of the C/L of Mack Road (gravel) running East and checked witnesses.

O.C.R.C. NE 68.90' Spike in 24" Oak SE 69.25' Spike in 15" Oak NNW 35.03' Spike in 24" Oak	L.C.R.C. L. 7417 P. 489 1978 N 80° E 68.48' 28" Oak	Record Survey L. 10304 P. 081 S 48° 55.68' MBT Riser	L.C.R.C. L. 12560 P. 595 N 85° 35.23' P.K. & Tag in S Side 32" Oak N 73° E 67.87' P.K. & Tag NW Side 28" Oak N 47° E 52.36 P.K. & Tag in NW Side 10" Locust
-----------------------------------------------------------------------------------------------------	--------------------------------------------------------	---------------------------------------------------------	----------------------------------------------------------------------------------------------------------------------------------------------------------------------

Kennedy Measures East 2821.4' to J-9
Buckerfield Measures South 2634.45' to I-10
King Measures North 2715.28' to I-8

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-9 Set a 5/8" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854" in place of found 1/2" iron rod. Also set monument box.

PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in E. Side 36" Oak N 12° W 100.93'
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in S Side 32" Oak N 85° W 35.23'
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NW Side 28" Oak N 73° E 67.87
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NW Side 10" Locust N 47° E 52.36
C/L Top MBT Riser S 48° E 55.68'
"X" Cut on Concrete Headwall S 16° E 53.10'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy Kolehouse Date 12/23/94
Surveyor's Michigan License No. 25854

