

SURVEY & REMONUMENTATION

FEB 29 5 01 1998

MAY - 1 1995

LIBER 15234 pg 535

OK - T. SMITH

LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

\$ 7.00 MISCELLANEOUS RECORDING

\$ 2.00 REMONUMENTATION

2 FEB 95 7:23 A.M. RECEIPT# 28
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

For corners in

Located in:	Addison Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11E</u>	<u>I-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Compliance with ACT 345, P.A. 1990

APPROVED ON: 11-30-94
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kolehouse, in a field survey on July 26 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-13 Per G.L.O. notes, J. Wampler set a post in 1817.

O.C.R.C. 1962
Stone
SSW 45.15' Spike 18" Maple
NW 73.80' Spike 18" Maple
NE 65.15' Spike 18" W Oak

L.C.R.C. L. 13889 P. 068 1982
NNW 56.25' to Nail & Tag #17623 in W Side Utl. Pole
NE 65.24' to PK & Tag #17623 in SE Side 27" Oak
SE 25.25' to PK & Tag #17623 in SW Side 18" Oak
SW 44.79' to Nail & O.C.R.C. Tag in N Side 36" Maple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13 Found 1/2" iron bar in monument box 2.5' South C/L Romeo Road (asphalt) running E-W and checked the following witnesses.

O.C.R.C. 1962
N 69° E 65.24' PK & Tag on SE Side 27" Oak

L.C.R.C. L. 13889 P. 068 1982
N 17° E 56.21' to Nail & Tag on W Side P. Pole
N 69° E 65.24' PK & Tag on SE Side 27" Oak
S 37° E 25.22' PK & Tag on SW Side 18" Oak
S 64° W 44.79' Nail & Tag on N Side 36" Maple

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 Set a 5/8" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854" in an existing monument box in place of found 1/2" iron bar.

- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in E Side Twin 6" Ash S 13° W 17.11'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SE Side 27" Oak N 69° E 65.24'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SW Side 18" Oak S 37° E 25.22'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in W Side P. Pole N 17° E 56.21'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in N Side 36" Maple S 64° W 44.79'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy Kolehouse
Surveyor's Michigan License No. 25854

Date 12/23/94

	A	B	C	D	E	F	G	H	I	J	K	L	N
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
6													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

