

SURVEY & REMONUMENTATION

FEB 29 01 1998

LIBER 15234 PG 536

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. P. W. H.

For corners in **COMMISSION**

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
2 FEB 95 7:23 A.M. RECEIPT# 28
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Located in:	Addison Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11E</u>	<u>J-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-12-94
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on July 28 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-1 This corner was not originally set by the G.L.O.

- Record Survey L. 11792 P. 231 1990
- P.K. in 18" Maple NNE 37.04'
- P.K. in 18" Maple NNW 30.37'
- P.K. in 18" Maple NW 44.75'
- P.K. in 10" Maple SSE 28.04'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-1 Found 1/2" rebar with cap 2.5' South of North line of Bordman Road (gravel) and checked witnesses.

- Record Survey L. 11792 P. 231 1990
- P.K. in SE Side 20" Maple N 38° E 36.98'
- P.K. in E Side 20" Maple N 04° W 30.32'
- P.K. in NE Side 20" Maple N 47° W 44.69'
- P.K. in W Side 12" Maple S 07° E 28.04'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1 Set a 5/8" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854" in place of found 1/2" iron rod

- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SE Side 20" Maple N 54° E 49.29'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SE Side 20" Maple N 38° E 36.98'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in E Side 20" Maple N 04° W 30.32'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NE Side 20" Maple N 47° W 44.69'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in W Side 12" Maple S 07° E 28.04'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/23/94
Surveyor's Michigan License No. 25854

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		6		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

