

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

COMMISSION

7.00 MISCELLANEOUS RECORDING \$ 2.00 REMONUMENTATION 2 FEB 95 7:23 A.M. RECEIPT# 2B PAID RECORDED - OAKLAND COUNTY LYNN D. ALLEN, CLERK/REGISTER OF DEEDS OK - T. SMITH

Compliance with ACT 345, P.A. 1990

APPROVED ON: 11-30-94 OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE Register of Deeds Stamp & File Number

Table with columns: Located in: Addison Township, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

4. Lot No. , Recorded Plat
5. Private Claims

I, Randy Kolehouse, in a field survey on July 26 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-13 Per G.L.O. notes, J. Wampler set a post in 1816.

- List of survey references: L.C.R.C. L. 5661 P. 581 1972, O.C.R.C. 1975, Kobs Survey 1984, L.C.R.C. L11792 P. 229 1991, etc.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13 Found 1/2" iron bar 1' North of C/L 32 Mile Road (asphalt) running E-W with an iron and brass cap in a monument box 8.32' West (N 1/4, Section 2, T4N, R11E). Checked the following witnesses.

- Witness list: L.C.R.C. L. 5661 P. 581 1972, O.C.R.C. 1975, L.C.R.C. L. 11792 P. 229, etc.

Avey Measures East to K-13 2640.91'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13 Set a 5/8" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854" in place of found 1/2" iron rod. Also set monument box.

- Monument descriptions: PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in E Side P. Pole N 05° W 39.78', etc.

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/23/94 Surveyor's Michigan License No. 25854

