

SURVEY &  
REMONUMENTATION

LISER 15234pc540

295019987

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE \$ 7.00 MISCELLANEOUS RECORDING  
Filing Requirement of Act 74, Mich. P.A. 1970 \$ 2.00 REMONUMENTATION

For corners in COMMISSION

<u>Oakland</u> (County)	Located in: Addison Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11E</u>	<u>K-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

2 FEB 95 7:23 A.M. RECEIPT# 2B  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

OK - T. SMITH

Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 12-12-94  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on July 28 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-1 Per G.L.O. notes, J. Wampler set a post in 1817.

M.E. Baldwin Date N/A	O.C.R.C. 1933	Record Survey L. 9783 P. 359 1986
Iron Pipe	Iron Pipe	1/2" Iron
Nail in 12" Hickory SW 91.0'	Nail in 12" Hickory SW 91.0'	North 23.59' Nail & Washer in Anchor Post
E-W Fence Line North 23.5'	E-W Fence Line North 23.5'	SW 91.23' Nail & Washer in 20" Hickory
Extended Line of Fence Line N West 3.30'	Extended Line of Fence Line N West 3.30'	SE 32.96' Nail & Washer in Anchor Post

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-1 Found 3/8" iron bar 3' North C/L Bordman Road (gravel) running E-W and 3' West of C/L Hagerman Road (gravel) running South. Checks the following witnesses.

Record Survey L. 9783 P. 359 1986  
North 24.03' Nail & Washer E Side Fence Cor. Post  
S 67° W 91.28' Nail in N Side 18" Hickory

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1 Set a 5/8" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854" in place of found 3/8" iron bar.

PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in E Side Fence Cor. Post North 24.03'  
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in N Side 18" Hickory S 67° W 91.28'  
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SW Side 20" Maple N 19° W 42.15'  
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NE Side P. Pole S 15° E 69.57'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy Kolehouse Date 12/27/94  
Surveyor's Michigan License No. 25854

