

**SURVEY &  
REMONUMENTATION**

LIBER **14833 PG 123**

94 **193367**

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

OK - T. SMITH

For corners in **COMMISSION**  
Oakland

	Located In:		Corner Code #
	5N	11E	
1. Public Land Survey	T _____ R _____	_____	K-5
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

\$ 7.00 MISCELLANEOUS RECORDING  
\$ 2.00 REMONUMENTATION  
15 JUL 94 7:29 A.M. RECEIPT# 1A  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS  
Compliance with  
ACT 345, P.A. 1990

APPROVED ON: 12-22-93  
OAKLAND COUNTY REMONUMENTATION  
PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Bruce Antcliff November 5 93

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19 \_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
K-5 GLO County Witnesses L.C.R.C. L. 8383, P. 21 (1982)  
Post NW 53.5' Nail in 36" Oak 1/2" Iron Pipe  
NE 25.4' Nail in 18" Oak N 80° E 29.05' Nail in 24" Oak  
SE 38.7' Nail in 18" Tw. Elm N 45° W 50.54' Nail in 40" Oak  
West 23.05' Spike in Tele Pole  
West 34.10' Corner Wood Fence Post  
Survey: H.J. Kobs (11/5/85)  
Fnd 1/2" Iron Bar  
P.K. Nail in Tele Pole WNW 23.23'  
P.K. Nail in 48" Oak W 50.60'  
P.K. Nail in 30" Maple NE 57.39'  
P.K. Nail in 40" Oak ENE 29.04'

L.C.R.C. L. 12161, P. 566 (1991)  
1/2" Iron Rod in Cen Line of Hagerman Rd  
West 23.00' NW in Power Pole  
N 88° E 28.66' PK/W in 22" Oak  
N 50° E 50.55' PK/W in 32" Oak

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-5 Found 3/4" rebar in center line Hagerman Road.  
Checks the following witnesses:

Survey: H.J. Kobs (11/5/85)  
P.K. Nail in Tele Pole WNW 23.23'  
P.K. Nail in 48" Oak W 50.60'

L.C.R.C. L. 8383, P. 21 (1982)  
N 80° E 29.05' Nail in 24" Oak  
N 45° W 50.54' Nail in 40" Oak

L.C.R.C. L. 12161, P. 566 (1991)  
Due west 23.00 ft N/W S Face Power Pole  
N 88° E 28.66 ft PK/W N Face 22" Oak  
N 50° E 50.33 ft PK/W NE Face 32" Oak

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-5 The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Set 5/8" rebar with standard Oakland County cap.

P.K. Nail and Brass Tag in West face of 8" Elm - South 07° E - 122.68'  
P.K. Nail and Brass Tag in P. Pole - West - 23.00'  
P.K. Nail and Brass Tag in NE face of 48" Oak - N 30° W - 49.78'  
P.K. Nail and Brass Tag in NE face of 22" Oak - N 88° E - 28.78'



Signed by Bruce Antcliff  
25826

Date 7-11-94

Surveyor's Michigan License No. \_\_\_\_\_