

SURVEY & REMONUMENTATION

LIBER 15234 PG 542

FEB 29 5019989

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION

For corners in

COMMISSION

<u>Oakland</u> (County)	Located in:	Addison Township	Corner Code #
1. Public Land Survey	T <u>5N</u>	R <u>11E</u>	<u>K-8</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

2 FEB 95 7:24 A.M. RECEIPT# 28
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

OK - T. SMITH
Compliance with
ACT 345, P.A. 1990

APPROVED ON: 11-30-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Randy Kolehouse, in a field survey on July 28 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-8 Per G.L.O. notes, J. Wampler set a post in 1817.

L.C.R.C. L. 8910 P. 679 1984
1/2" Iron Bar
Nail in 12" Oak SSW 13.75'
Nail in 24" Oak South 11.56'
Nail in 20" W Cherry SE 24.51'

Kobs-King Surveys 1984-1989
1/2" Iron Bar
Nail in 12" Oak SSW 13.75'
Nail in 24" Oak South 11.56'
Nail in 20" W Cherry SE 24.51'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8 Found 1/2" rebar on tree line running E-W, 1.5' North of fence running West and 2.5' West of fence running North. Checked following witnesses.

L.C.R.C. L. 8910 P. 679 1984
S 40° W 13.75' Nail in NW Side 12" Oak
S 11.56' Nail in W Side 24" Oak
S 30° E 24.59' Nail in SW Side Twin 20" Cherry

Kobs & King Measures South to K-9 2740.02'
Kobs & King Measures North to K-7 2670.76'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8 Set a 5/8" rebar in a very large stone (stone 8" M/L below surface) with brass cap stamped "Oakland County Remonumentation P.S. #25854" in place of found 1/2" iron rod.

PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in E Side 24" Oak N 16° W 32.03'
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NW Side 12" Oak S 40° W 13.75'
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in W Side 24" Oak S 11.56'
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in SW Side Twin 20" Cherry S 30° E 24.59'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.



Signed by Randy J. Kolehouse

Date 12/23/94

Surveyor's Michigan License No. 25854