

SURVEY &
REMONUMENTATION

LIBER 14833 PG 125

94 193369

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

OK - T. SMITH

For corners in
Oakland

COMMISSION

	Located In:		Corner Code #
	5N	11E	
1. Public Land Survey	T	R	L-1
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

\$ 7.00 MISCELLANEOUS RECORDING
\$ 2.00 REMONUMENTATION
15 JUL 94 7:29 A.M. RECEIPT# 1A
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS
ACT 345, P.A. 1990

APPROVED ON: 2-2-94
OAKLAND COUNTY REMONUMENTATION
PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	N
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Bruce Antcliff November 8 93

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-1	GLO Post	County Witnesses NW - 26.5' - USGS BM SE - 158.5' - Nail in 20" Pear SSE - 56.7' - Nail in 12" Cherry	L.C.R.C. L. 6663, P. 651 (1976) 1/2" Pipe PK Nail in 6" Ash - NW - 70.31' PK Nail in Tel. Pole - NE - 62.91' PK Nail in Anchor Post - SE - 36.38'
			Survey L. 6663 P. 646 (1976) Same as L.C.R.C. L. 6663, P. 651

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-1	Found 1/2" Pipe at center line intersection of Secord Lake and Bordman Road. Checks the following witnesses:	L.C.R.C. L.6663, P. 651 (1976) PK Nail in 6" Ash - NW - 70.31' PK Nail in Tel. Pole - NE - 62.91'	Survey L. 6663 P. 646 (1976) Same as L.C.R.C. L. 6663, P. 651
-----	---	---	--

Handwritten signature/initials

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1 The selected location of a corner, although not established by the original government survey, is accepted as the best available evidence of the position of the corner.
Set 5/8" rebar with standard Oakland County cap.

P.K. Nail and Brass Tag in W face P. Pole - N 40° E - 63.00'
P.K. Nail and Brass Tag in E face 12" Ash - N 10° W - 70.45'
P.K. Nail and Brass Tag in W face Tw. 12" Ash - S 20° E - 51.36'
P.K. Nail and Brass Tag in SW face 20" Ash - N 85° E - 109.09'



Signed by Bruce Antcliff 25826
Surveyor's Michigan License No. _____

Date 7-11-94