

SURVEY & REMONUMENTATION

LIBER 15234 PG 547

FEB 29 5 01 99 94

OK - T. SMITH

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 § 7.00 MISCELLANEOUS RECORDING

For corners in **COMMISSION**

_____	Oakland (County)	Located in:	Addison Township	Corner Code #
1. Public Land Survey		T <u>5N</u>	R <u>11E</u>	<u>L-9</u>
		T _____	R _____	_____
		T _____	R _____	_____
		T _____	R _____	_____
2. Property Controlling in Section		S _____	T _____	R _____
		S _____	T _____	R _____
3. Miscellaneous Property in Sec.		S _____	T _____	R _____
		S _____	T _____	R _____

§ 2.00 REMONUMENTATION
2 FEB 95 7:25 A.M. RECEIPT# 2B
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990

APPROVED ON: 11-30-94
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randy Kolehouse, in a field survey on July 19 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- L-9 Per G.L.O. notes, J. Wampler set a post in 1817.
- | | | |
|---|---|--|
| L.C.R.C. L. 8075 P. 757 1981
N 60° E 60.50' Nail in 36" Oak
S 45° E 54.38' to PK in 30" Oak
S 25° W 38.14' PK in 28" Oak | L.C.R.C. L. 8910 P. 680 1984
1/2" Iron Bar
NE 62.06' PK in 36" Oak
SSW 38.35' PK in 24" Oak
SE 54.41' PK in 30" Oak | Kobs Surveys 1983, 1987, 1988
1/2" Iron Bar
NE 62.06' PK in 36" Oak
SSW 38.35' PK in 24" Oak
SE 54.41' PK in 30" Oak |
|---|---|--|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-9 Found 1/2" iron bar at C/L of Mack Road (gravel) running E-W and checked following witnesses.
- | | |
|---|--|
| L.C.R.C. L. 8075-757/8916-680
N 60° E 60.47' Nail in Remains of 36" Oak
S 45° W 54.42' PK in NE Side 30" Oak
S 37° W 38.28' PK in E Side 24" Oak | L.C.R.C. L. 8910 P. 680 1984
1/2" Iron Bar
SSW 38.35' PK in 24" Oak
SE 54.41' PK in 30" Oak |
|---|--|

Kobs Measures 2643.86' to K-9
Kobs Measures 2642.28' to L-10

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-9 Set a 5/8" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854" in place of found 1/2" iron rod.
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in E Side 24" Oak S 37° W 38.28'
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NE Side 30" Oak S 45° W 54.42'
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in W Side Remains of 36" Oak N 60° E 60.47'
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NE Side 17" Oak S 59° E 79.10'
SE Cor. Fndn. Hse. #1485 (Mack Road) N 23° W 200.52' S

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/23/94
Surveyor's Michigan License No. 25854

