
LISER 15234PC 548



MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE, 7.00 MISCELLANEOUS RECORDING

For comers in CON Oakland (County)		#MISSION Filing Requirement of Act 74, Mich. P.A			1970 7.00 HISCELLANEOUS RECORDING \$ 2.00 REMONUMENTATION \$ 2 FEB 95 7:25 A.M. RECEIPT# 2B	
		Located in: Add Town			PAID RECORDED - OAKLAND COUNTY LYNN D. ALLEN, CLERK/REGISTER OF DEEDS	
1.	Public Land Survey	T <u>5N</u> T T	_ R _ R	<u>L-11</u>	OK - T. SMITH Compliance with ACT 345, P.A. 1990	
2. 3.	Property Controlling in Section Miscellaneous Property in Sec.	S T S T	R R R		APPROVED ON: 12-12-94 OAKLAND COUNTY REMONUMENTATION PÉER GROUP COMMITTEE Register of Deeds Stamp & File Number	
4. 5.	Lot No Private Claims				ABCDEFGHIJKL	
	,				2 - 6 5 - 4 - 3 - 2 - 1	

I, Randy Kolehouse, in a field survey on July 18 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- L-11 Per G.L.O. notes, J. Wampler set a post in 1817.

Oakland Co. Road Comm. 1933

1" Iron

NNE 19.85' Stone Pillar

SSE 34.85' Nail in 10" Blk. Oak

L.C.R.C. L. 7448 P. 116 1979

1/2" Iron

North 26.30' to SW Cor. Conc. Slab at Fence Cor.

S 40° E 28.48' Nail & Flasher 42" Oak S 10° W 41.60' Nail & Flasher in Utl. Pole Kobs Survey 1991 1/2" Iron Bar

SE 29.82' P.K. in 42" Oak SSW 42.17' P.K. in P. Pole NNE 25.83' SE Cor. Conc. Cap on Stone Pillar

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- L-11 Found 1/2" iron bar 3' M/L North of the C/L of Brewer Road (gravel) running E-W. Checked the following witnesses.

L.C.R.C. L. 7448 P. 116 1979 North 25.95' SW Cor. Conc. Slab on Fence Post (Stone) S 40° E 28.83' Nail & Flasher N Side 42* Oak S 10° W 41.88' Nail & Flasher W Side P. Pole

Kobs Measures West 2641.86' to K-11 Kobs Measures North 2560.84' to L-10

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- L-11 Set a 5/8" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854" in place of found 1/2" iron rod.

PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in S Side 12" Oak N 57° W 42.86'

NW Cor. Hse. Fndn. Hse. #1505 N 37° E 149,90' SW Cor. Conc. Slab on Stone Fence Post North 25.95'

PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in N Side 42" Oak S 40° E 28.83'

PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in W Side P. Pole S 10° W 41.88'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original comer.

RANDY I.
KOLEHOUSE
LAND
SURVEYOR
25854

O LAND SURE