

SURVEY & REMONUMENTATION

LICER. 15234pc549

FEB 29 5 01 99 96

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE

OK - T. SMITH

Filing Requirement of Act 74, Mich. P.A. 1970 \$ 7.00 MISCELLANEOUS RECORDING

For corners in **COMMISSION**

Oakland (County)	Located in:	Addison Township	Corner Code #
1. Public Land Survey	T <u>5N</u>	R <u>11E</u>	<u>L-13</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

\$ 2.00 REMONUMENTATION
2 FEB 95 7:25 A.M. RECEIPT# 28
PAID RECORDED - OAKLAND COUNTY
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS

Compliance with ACT 345, P.A. 1990

APPROVED ON: 12-12-94
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Randy Kolehouse, in a field survey on July 26 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-13 Per G.L.O. notes, J. Wampler set a post in 1816.

- | | |
|--|--|
| O.C.R.C. 1975
1/2" Solid Iron
NW 85.30' Nail & Washer in D.E. Pole
N 46.93' Nail & Washer in D.E. Pole
S 34.00' Nail & Washer in M.B.T. Pole | L.C.R.C. L. 8854 P. 260 1984
5/8" Iron Bar in Mon. Box
WNW 78.00' Chiseled Cross in NE Side 6" Steel Post
N 46.93' Form Nail & O.C.R.C. Tag in P. Pole
S 34.00' Form Nail & O.C.R.C. Tag in M.B.T. Pole
SW 75.92' P.K. in 21" Elm |
|--|--|

Record Survey L. 12114 P. 264
Same Wits. as L.C.R.C. L 8854 P. 260

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 Found a 5/8" iron bar with brass cap stamped Oakland County Remonumentation P.S. #22445 as set by Grant Ward in monument box 2' M/L North of the C/L of Romeo Road running E-W. Checks the following witnesses.

- | | |
|--|---|
| O.C.R.C. 1975
N 53° W 85.23' in D.E. Pole | L.C.R.C. L. 8854 P. 260 1984
N 57° W 77.90' Chiseled "X" in N Side 6" Steel Sign Post
N 05° E 46.57' Nail & O.C.R.C. Tag in W Side D.E. Pole
S 34.03' Nail & O.C.R.C. Tag in W Side D.E. Pole
S 50° W 75.96' P.K. & Tag (G.L.O. 78796) in NW Side 21" Elm |
|--|---|

Kobs Measures East 2661.8' to M-13

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 5/8" iron bar with brass cap stamped "Oakland County Remonumentation P.S. #22445" in an existing monument box.

- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NE Side D.E. Pole N 53° W 85.23' Chiseled "X" in N Side 6" Steel Sign Post N 57° W 77.90'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in W Side D.E. Pole N 05° E 46.57'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in W Side D.E. Pole S 34.03'
- PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in NW Side 21" Elm S 50° W 75.96'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 12/23/94
Surveyor's Michigan License No. 25854

