

**SURVEY & REMONUMENTATION**

LIBER 15234 PG 551

FEB 29 5 01 99 98

MAY - 1 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

7.00 MISCELLANEOUS RECORDING  
2.00 REMONUMENTATION  
2 FEB 95 7:25 A.M. RECEIPT# 2B  
PAID RECORDED - OAKLAND COUNTY  
LYNN D. ALLEN, CLERK/REGISTER OF DEEDS  
**OK - T. SMITH**

For corners in

<u>Oakland</u> (County)	Located in: Addison Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>11E</u>	<u>M-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Compliance with ACT 345, P.A. 1990  
APPROVED ON: 12-12-94  
OAKLAND COUNTY REMONUMENTATION PEER GROUP COMMITTEE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on June 19 94, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

M-5 Per G.L.O. notes, J. Wampler set a post in 1817.

Record Survey L. 9418 P. 88 1986  
5/8" Iron Bar  
P.K. Nail in End Fence Post SW 62.35'  
Chis. Cross in Steel Anchor Post SE 78.51'  
P.K. & Washer in 10" W Cherry NW 23.26'

Record Survey L. 11224 P. 837 1986  
Same Wits. as  
Record Survey 9418 P. 88

Heil Survey 1989  
Same Wits. as  
Record Survey 9418 P. 88

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-5 Found a 5/8" iron bar 2.5' West of C/L DeQuindre Road (gravel) running N-S 22.5' North of C/L 36 Mile Road (gravel) running East 30.89' North of A-5 Bruce Twp. T5N R12E Macomb Co. and checked the following witnesses.

"X" Cut in Steel Anchor Post S 30° E 78.61'  
P.K. in E Side Tw. 8" Cherry N 45° W 23.36'

Kobs Measures West 2672.94' to L-5  
Kobs Measures South 2628.39' to M-6

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5 Set a 5/8" rebar with brass cap stamped "Oakland County Remonumentation P.S. #25854" in place of found 5/8" iron bar.

3/8" Iron Bar S 0° W 30.89' (A-5 T5N R12E)  
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in N Side Twin 20" Oak N 85° W 43.56'  
"X" Cut in N End Steel Culvert S 34° W 35.55'  
"X" Cut in Steel Anchor Post S 30° E 78.61'  
PK Nail & Tag Stamped "Oakland Co. Remonumentation P.S. #25854" in E Side Tw. 8" Cherry N 45° W 23.36'

The selected location is accepted by the Contractor and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J Kolehouse Date 12/23/94  
Surveyor's Michigan License No. 25854

	A	B	C	D	E	F	G	H	I	J	K	L	N
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

